


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Stafford	Fraction 1/4 C 1/4 NW 1/4	Section number 7	Township number T 22 S R 14 E/W	Range number
2. Distance and direction from nearest town or city: 1-S 1-W 1/4-S of Radium, Ks. East into field. Street address of well location if in city:			3. Owner of well: Dave Marmie R.R. or street: 4210 Falcon St. City, state, zip code: Great Bend, Kansas 67530		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		
5. Type and color of material			From	To	6. Bore hole dia. 108 in. Completion date 4-27-78 Well depth 108 ft.
Sandy top soil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Brown gray clay			2	14	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Sand & gravel w/clay breaks			14	17	9. Casing: Material steel Height: Above or below 108 Threaded ☐ Welded ☐ Surface 24 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 108 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7
Sand & gravel			17	60	10. Screen: Manufacturer's name Doerrs Type steel Dia. 16 Slot 3/16 Length 32 Set between 76 ft. and 108 ft. Gravel pack? ☒ Size range of material 3/4 3/8
Brown clay			60	64	11. Static water level: 22 ft. below land surface Date 4-13-78 mo./day/yr.
Fine sandy clay			64	74	12. Pumping level below land surfaces: 57 ft. after 1 hrs. pumping 600 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1000 g.p.m.
Medium sand 1/8" dia. tops-loose			74	104	13. Water sample submitted: ☒ Yes ☐ No Date 4-13-78 mo./day/yr.
Clay			104	105	14. Well head completion: ☐ Pitless adapter ☐ Inches above grade
Sand & gravel			105	107	15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
Clay			107	110	16. Nearest source of possible contamination: ft. 600 Direction NW Type gaswell Well disinfected upon completion? HTH Yes ☐ No
					17. Pump: ☐ Not installed Manufacturer's name W.L.R. Model number 3-12KBH HP 80 Volts ☐ Length of drop pipe 100 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation: 1959' Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed Sandy Kilgore Date 7-1-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5