

1 LOCATION OF WATER WELL:		Fraction		Near the Center		Section Number		Township Number		Range Number	
County: Stafford		1/4		1/4 NE 1/4		15		T 22 S		R 14 XW	
Distance and direction from nearest town or city street address of well if located within city?											
Approx. 2 1/4 south and 2 3/4 mi. West of ■ ■ Seward, KS											
2 WATER WELL OWNER: Don Kirkman											
RR#, St. Address, Box # : Route 5 - Box 150											
City, State, ZIP Code : Great Bend, KS 67530											
Board of Agriculture, Division of Water Resources											
Application Number: 36505											
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:				4 DEPTH OF COMPLETED WELL: 133 ft. ELEVATION: unknown							
				Depth(s) Groundwater Encountered 1. 21 ft. 2. ft. 3. ft.							
				WELL'S STATIC WATER LEVEL 21 ft. below land surface measured on mo/day/yr 8-30-84							
				Pump test data: Well water was not ck'd ft. after hours pumping gpm							
				Est. Yield 950 gpm: Well water was ft. after hours pumping gpm							
				Bore Hole Diameter 24 in. to 133 ft., and in. to ft.							
WELL WATER TO BE USED AS:											
5 Public water supply 8 Air conditioning 11 Injection well											
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)											
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well											
Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted											
Water Well Disinfected? Yes No X											
5 TYPE OF BLANK CASING USED:											
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped											
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded XX											
7 Fiberglass Threaded											
Blank casing diameter 16 in. to 73 ft., Dia in. to ft., Dia in. to ft.											
Casing height above land surface 12 in., weight 36.87 lbs./ft. Wall thickness or gauge No. 219											
TYPE OF SCREEN OR PERFORATION MATERIAL:											
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement											
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)											
9 ABS 12 None used (open hole)											
SCREEN OR PERFORATION OPENINGS ARE:											
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)											
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes											
7 Torch cut 10 Other (specify) DOERR Bridge Slot											
SCREEN-PERFORATED INTERVALS: From 73 ft. to 133 ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
GRAVEL PACK INTERVALS: From 10 ft. to 133 ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other											
Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.											
What is the nearest source of possible contamination:											
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well											
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well											
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)											
13 Insecticide storage FIELD											
Direction from well? All How many feet?											
FROM TO LITHOLOGIC LOG FROM TO LITHOLOGIC LOG											
0 14 Fine sand topsoil											
14 35 Sandy brown clay											
35 38 Sand & sandy soft tan clay											
38 108 Sand & gravel, med. some coarse w/ a few thin clay streaks											
108 113 Green clay											
113 116 Sand & gravel, fine w/a lot of clay streaks											
116 133 Sand & gravel, fine to med. w/a few thin clay streaks											
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8/30/84 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 9-14-84 under the business name of Clarke Well & Eq., Inc. by (signature)											
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.											