

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 1/4 CNE 1/4	Section number 17	Township number T 22 S R	Range number 14 NW
2. Distance and direction from nearest town or city: 15 1/2 Miles Northwest of St. John, KS Street address of well location if in city:				3. Owner of well: Bud Pinkston R.R. or street: Rural Route City, state, zip code: Seward, KS 67577		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>24</u> in. Completion date <u>3-8-77</u> Well depth <u>94</u> ft.		
		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material <u>steel</u> Height <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia <u>16</u> in. to <u>50</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7 ga.</u>		
				10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot/gauze <u>1/8"</u> Length <u>44"</u> Set between <u>50</u> ft. and <u>94</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u>		
				11. Static water level: <u>13</u> ft. below land surface Date <u>12-23-76</u> 12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.		
5. Type and color of material		From	To	13. Water sample submitted: <u> </u> mo./day/yr. Yes ☒ No ☐ Date <u> </u>		
clay & fine sand		0	13	14. Well head completion: ☐ Pitless adapter <u>12</u> Inches above grade		
sand & gravel		13	24	15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
clay		24	30	16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No ☐		
sand & gravel & thin clay streak @ 35' & 40'				17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless Pumps</u> Model number <u>12MB-4</u> HP <u>50</u> Volts <u>460</u> Length of drop pipe <u>60</u> ft. capacity <u>900</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
& 50' & 53'		30	78	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. <u>185</u> Business name License No. Address <u>Great Bend, KS 67530</u> Signed <u>[Signature]</u> Date <u>3-11-77</u> Authorized representative		
clay		78	80			
sand & gravel		80	94			
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5