

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Stafford</u>	Fraction <u>2/16 NE 1/4</u>	Section number <u>23</u>	Township number <u>T 22 S</u>	Range number <u>R 14 E</u>
2. Distance and direction from nearest town or city: <u>1W/3 1/4 S - 1/4 W of Seaward, KS</u>			3. Owner of well: <u>DAVE MARMIC</u> R.R. or street: <u>4210 Faxon St.</u> City, state, zip code: <u>Great Bend, KS</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>29</u> in. Completion date <u>4-14-76</u> Well depth <u>133</u> ft.		
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
5. Type and color of material		From	To	9. Casing: Material <u>Steel</u> Height: <u>Above or below</u> Threaded ☐ Welded ☒ Surface <u>18</u> in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. <u>16</u> in. to <u>133</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>7</u>		
Top Soil		0	2	10. Screen: Manufacturer's name <u>Duerr</u> Type <u>Steel</u> Dia. <u>16</u> Slot/gauge <u>3/16</u> Length <u>60</u> Set between <u>73</u> ft. and <u>133</u> ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material <u>1/2 3/4 3/8</u>		
Brown Clay		2	6	11. Static water level: <u>13</u> ft. below land surface Date <u>8-18-75</u> mo./day/yr.		
Fine Sand & Sandy Clay		6	48	12. Pumping level below land surfaces: <u>17</u> ft. after <u>112</u> hrs. pumping <u>1400</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.		
Med. Sand & Gravel		48	58	13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>9-19-75</u> mo./day/yr.		
Brown Clay		58	60	14. Well head completion: ☐ Pitless adapter ☐ Inches above grade		
Sand & Gravel Med. loose clean		60	84	15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
Yellow Brown Clay		84	86	16. Nearest source of possible contamination: ft. <u>400</u> Direction <u>N</u> Type <u>Canal</u> Well disinfected upon completion? ☐ Yes ☐ No		
Sand & Gravel some Clay		86	93	17. Pump: ☐ Not installed Manufacturer's name <u>WLR</u> Model number <u>3-5M-12</u> HP <u>50</u> Volts <u>460</u> Length of drop pipe <u>70</u> ft. capacity <u>1000</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Yellow Brown light Gray Clay		93	100	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz - Bemis</u> <u>134</u> Business name <u>Great Bend, KS.</u> License No. <u> </u> Address <u> </u> Signed <u>Thelma Reden</u> Date <u>9/25/75</u> Authorized representative		
Sand & Gravel Fine, loose some Clay		100	128			
Blue Shale		128	131			
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5