

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 1/4 CNE 1/4	Section number 28	Township number T 22 S R 14 E W
2. Distance and direction from nearest town or city: 11 1/2 miles Northwest of St. John, KS Street address of well location if in city:			3. Owner of well: Stan Christiansen R.R. or street: Route 3 City, state, zip code: Hudson, KS 67545		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 			
5. Type and color of material		From	To	6. Bore hole dia. 24 in. Completion date 3-8-77 Well depth 80 ft.	
Fine sand & clay streaks		0	27	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Gravel & clay streaks		27	69	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Clay		69	72	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 40 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.	
				10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot/gauge 1/8" Length 40' Set between 40 ft. and 80 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 3/8-200	
				11. Static water level: ☐ mo./day/yr. 15'7" ft. below land surface Date 2-14-77	
				12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
				13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No Date ☐	
				14. Well head completion: ☐ Pitless adapter 12 Inches above grade	
				15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
				16. Nearest source of possible contamination: Field ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No	
				17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Model number 12MB-4 HP 60 Volts 460 Length of drop pipe 70 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
		(Use a second sheet if needed)			
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Equip., Inc. 185 Business name Great Bend, KS 67530 License No. 3-11-77 Address 3-11-77 Signed [Signature] Date 3-11-77 Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5