

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Stafford</b>	Fraction <b>1/4 C 1/4 SW 1/4</b>	Section number <b>30</b>	Township number <b>T 22 S R 14 E</b>	Range number <b>14 E</b>
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: <b>Clayton Morrison</b> R.R. or street: <b>2706 Pheasant St.</b> City, state, zip code: <b>Great Bend, Ks. 67530</b>			
4. Locate with "X" in section below:			Sketch map:		6. Bore hole dia. <b>29</b> in. Completion date <b>11-2-76</b> Well depth <b>70</b> ft.	
					7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
5. Type and color of material			From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Top Soil			0	2	9. Casing: Material <b>steel</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <b>16</b> in. to <b>70</b> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <b>7</b>	
Sandy Brown Clay			2	14	10. Screen: Manufacturer's name <b>Doerrs</b> Type <b>steel</b> Dia. <b>16</b> Slot <b>3/16</b> Length <b>20</b> Set between _____ ft. and _____ ft. _____ ft. and _____ ft.	
Fine Sand			14	17	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>3/4 3/8</b>	
Sandy Brown Clay and Fine Sand			17	32	11. Static water level: _____ mo./day/yr. <b>17</b> ft. below land surface Date <b>4-6-76</b>	
Sand and Gravel Clean Coarse Loose			32	70	12. Pumping level below land surfaces: <b>MNC</b> <b>17</b> ft. after <b>1</b> hrs. pumping <b>800</b> g.p.m. <b>27</b> ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>1000</b> g.p.m.	
<del>Light Gray Clay</del>			70	75	13. Water sample submitted: _____ mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <b>4-6-76</b>	
Brown and Gray Clay			75	127	14. Well head completion: _____ <b>18</b> inches above grade	
Hard Reddish Black Sand and Sand Rock with			127	135	15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.	
Yellow Brown Light Grey Clay					16. Nearest source of possible contamination: _____ ft. <b>100</b> Direction <b>NW</b> Type <b>Corbell</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
					17. Pump: _____ Not installed Manufacturer's name <b>Western Land Roller</b> Model number <b>3CH10</b> HP <b>30</b> Volts _____ Length of drop pipe <b>59</b> ft. capacity <b>1000</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley				Business name <b>Rosencrantz-Bemis</b> License No. <b>134</b> Address <b>Great Bend, Ks.</b> Signed <b>Fredia Wade</b> Date <b>1-22-77</b> Authorized representative		

22 140 30 1/4 1/4 SW

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5