


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction Center 1/4 1/4 SW 1/4	Section number 35	Township number T 22 S	Range number R 14 E
2. Distance and direction from nearest town or city: Approx. 8 1/2 Miles NW of St. John, KS Street address of well location if in city:				3. Owner of well: Loyd Ratts R.R. or street: Route 4 City, state, zip code: St. John, KS 67576		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 24 in. Completion date 7-2-79 Well depth 75 ft. Pump Set 7-10-79		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
5. Type and color of material		From	To	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 35 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.		
Top Soil		0	5	10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot gauge 1/8" Length 40' Set between 35 ft. and 75 ft. ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200		
Brown clay		5	19	11. Static water level: ☐ mo./day/yr. 18' 6" ft. below land surface Date 7-2-79		
Clay & sand streaks		19	35	12. Pumping level below land surfaces: Not Checked ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
Sand & gravel		35	68	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
Brown hard clay		68	75	14. Well head completion: ☐ Pitless adapter 12 Inches above grade		
				15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Co. Model number 12LB-3 HP * Volts --- Length of drop pipe 70 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		* Owner's Gear Drive was used		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Address Rt. 1 - Great Bend, KS 67530 Signed [Signature] Date 7-27-79 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5