


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>Pawnee</u>	Fraction <u>SE 1/4 SW 1/4 NW 1/4</u>	Section number <u>23</u>	Township number <u>T 22 S</u>	Range number <u>R 15 E</u>
2. Distance and direction from nearest town or city: <u>road 1 mi west 2 1/2 south west side of road</u> Street address of well location if in city:			3. Owner of well: <u>Keith Mull</u> R.R. or street: <u>Rt. #1</u> City, state, zip code: <u>Pawnee Rock, Kansas 67567</u>		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>29</u> in. Completion date <u>2/10/77</u> Well depth <u>77</u> ft.	
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
Top soil		0	1	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
clay		1	14	9. Casing: Material <u>steel</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>77</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>7</u>	
Fine sand		14	20	10. Screen: Manufacturer's name <u>Doerrs</u> Type <u>steel</u> Dia. <u>16"</u> Slot <u>3/16</u> Length <u>28' m/c</u> Set between <u>49</u> ft. and <u>77</u> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>3/8x3/4</u>	
Sand and clay		20	27	11. Static water level: <u>20</u> ft. below land surface Date <u>7/28/76</u> mo./day/yr.	
Good clean sand and gravel		27	78	12. Pumping level below land surfaces: <u>31</u> ft. after <u>1</u> hrs. pumping <u>600</u> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.	
Green clay		78	80	13. Water sample submitted: <u>7/28/76</u> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Yellow clay		80	101	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
Rock		101	106	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
Sand Rock		106	108	16. Nearest source of possible contamination: ft. <u>511</u> Direction <u>west</u> Type <u>corral</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
Shale		108	120	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>W.L.R.</u> Model number <u>1-14CHC</u> HP <u>25</u> Volts <u>460</u> Length of drop pipe <u>60</u> ft. capacity <u>750</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)					
18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz-Pemis</u> <u>134</u> Business name <u>Great Bend, Ks</u> License No. <u>67530</u> Address <u>Sandy Hill Ave</u> Date <u>6/23/77</u> Signed <u>[Signature]</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5