

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number																																				
County: Pawnee		NE ¼ NE ¼ NE ¼	28	T 22 S	R 15W E/W																																				
Distance and direction from nearest town or city street address of well if located within city? 6E, 3N of Zook, Ks.																																									
2 WATER WELL OWNER: Dean Zook RR#, St. Address, Box # : RR 2 Board of Agriculture, Division of Water Resources City, State, ZIP Code : Larned, Ks. 67550 Application Number:																																									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 77 ft. ELEVATION: unknown Depth(s) Groundwater Encountered 1. 50 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 50 ft. below land surface measured on mo/day/yr 5-16-98 Pump test data: Well water was ft. after hours pumping gpm Est. Yield 12 gpm; Well water was ft. after hours pumping gpm Bore Hole Diameter .8 in. to .77 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No																																							
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 5 in. to 57 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 12 in., weight 2.8 lbs./ft. Wall thickness or gauge No. Sch. 40 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes SCREEN-PERFORATED INTERVALS: From 57 ft. to 77 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 37 ft., From 40 ft. to 77 ft. From ft. to ft., From ft. to ft.																																									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 20 ft., From 37 ft. to 40 ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) shed Direction from well? West How many feet? 55																																									
<table border="1"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0</td><td>3</td><td>top soil</td><td></td><td></td><td></td></tr><tr><td>3</td><td>28</td><td>clay</td><td></td><td></td><td></td></tr><tr><td>28</td><td>39</td><td>sand and gravel</td><td></td><td></td><td></td></tr><tr><td>39</td><td>57</td><td>clay</td><td></td><td></td><td></td></tr><tr><td>57</td><td>77</td><td>sand rock</td><td></td><td></td><td></td></tr></tbody></table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	3	top soil				3	28	clay				28	39	sand and gravel				39	57	clay				57	77	sand rock			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																				
0	3	top soil																																							
3	28	clay																																							
28	39	sand and gravel																																							
39	57	clay																																							
57	77	sand rock																																							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-16-98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 186 This Water Well Record was completed on (mo/day/yr) 5-22-98 under the business name of Kelly's Water Well Service, Inc. by signature Kathryn L And																																									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.																																									