


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82g-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Pawnee</b>	Fraction <b>SW 1/4 SE 1/4 NE 1/4</b>	Section number <b>16</b>	Township number <b>T 22 S</b>	Range number <b>R 16 E W</b>
2. Distance and direction from nearest town or city: <b>2-S 3/4-E of Larned, Ks.</b> Street address of well location if in city:			3. Owner of well: <b>Jerry Marmic</b> R.R. or street: <b>Great Bend, Ks. 67530</b> City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		
5. Type and color of material			From	To	6. Bore hole dia. <b>24</b> in. Completion date <b>8-25-78</b> Well depth <b>75</b> ft.
<b>Sandy top soil</b>			<b>0</b>	<b>2</b>	7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
<b>Clay</b>			<b>2</b>	<b>31</b>	8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> <input type="checkbox"/> Low <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
<b>Sand &amp; gravel</b>			<b>31</b>	<b>49</b>	9. Casing: Material <b>steel</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <b>16</b> in. to <b>75</b> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <b>7</b>
<b>Clay</b>			<b>49</b>	<b>60</b>	10. Screen: Manufacturer's name <b>Oacrrs</b> Type <b>steel</b> Dia. <b>16" m/c</b> Slot/groove <b>3/16</b> Length <b>16</b> Set between <b>75</b> ft. and <b>59</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/2 3/4 3/8</b>
<b>Sand &amp; gravel</b>			<b>60</b>	<b>68</b>	11. Static water level: _____ mo./day/yr. <b>34</b> ft. below land surface Date <b>6-28-78</b>
<b>Clay</b>			<b>68</b>	<b>76</b>	12. Pumping level below land surfaces: <b>54</b> ft. after <b>1</b> hrs. pumping <b>400</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>650</b> g.p.m.
<b>Blue clay</b>			<b>76</b>	<b>96</b>	13. Water sample submitted: _____ mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <b>6-28-78</b>
<b>Fire clay</b>			<b>96</b>	<b>97</b>	14. Well head completion: Pitless adapter _____ Inches above grade
					15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
					16. Nearest source of possible contamination: ft. <b>1 mile</b> Direction <b>N</b> Type <b>feed yard</b> Well disinfected upon completion? <b>Hill</b> Yes <input type="checkbox"/> No <input type="checkbox"/>
					17. Pump: Not installed Manufacturer's name <b>W. Z. R.</b> Model number <b>510CNC</b> HP <b>40</b> Volts <b>460</b> Length of drop pipe <b>60</b> ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
18. Elevation:			19. Remarks:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley			(Use a second sheet if needed)		
			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Rosencrantz-Demis</b> <b>134</b> Business name License No. Address <b>Great Bend, Ks 67530</b> Signature <b>Sandy Hilborn</b> Date <b>10/18/78</b> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5