

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

17410

1 LOCATION OF WATER WELL: County: Pawnee		Fraction 1/4 CW 1/4 NW 1/4 NE 1/4		Section Number 23		Township No. T 22 S		Range Number R 16 <input type="checkbox"/> E <input checked="" type="checkbox"/> W																																																																			
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here <input type="checkbox"/> Approximately 3.5 miles south and 2.5 miles east of Larned.				Global Positioning System (GPS) information: Latitude: 38.128995 (in decimal degrees) Longitude: -99.049474 (in decimal degrees) Elevation: Unknown Datum: <input type="checkbox"/> WGS 84, <input checked="" type="checkbox"/> NAD 83, <input type="checkbox"/> NAD 27 Collection Method: <input checked="" type="checkbox"/> GPS unit (Make/Model: WAAS) <input type="checkbox"/> Digital Map/Photo, <input type="checkbox"/> Topographic Map, <input type="checkbox"/> Land Survey Est. Accuracy: <input type="checkbox"/> <3 m, <input checked="" type="checkbox"/> 3-5 m, <input type="checkbox"/> 5-15 m, <input type="checkbox"/> >15 m																																																																							
2 WATER WELL OWNER: David Blackwell RR#, Street Address, Box #: 901 Bluff Drive City, State, ZIP Code: Larned, KS 67550																																																																											
3 LOCATE WELL WITH AN "X" IN SECTION BOX: <div style="text-align: center;">N W E S 1 mile</div>		4 DEPTH OF COMPLETED WELL 114 ft. Depth(s) Groundwater Encountered (1) 46 ft. (2) 114 ft. (3) 01/03/13 ft. WELL'S STATIC WATER LEVEL 46 ft. below land surface measured on mo/day/yr Pump test data: Well water was not checked ft. after 01/03/13 hours pumping 0 gpm EST. YIELD 30 gpm. Well water was 114 ft. after 01/03/13 hours pumping 0 gpm Bore Hole Diameter 30 in. to 114 ft., and 01/03/13 in. to 01/03/13 ft. WELL WATER TO BE USED AS: <input type="checkbox"/> Public water supply <input type="checkbox"/> Geothermal <input type="checkbox"/> Injection well <input type="checkbox"/> Domestic <input type="checkbox"/> Feedlot <input type="checkbox"/> Oil field water supply <input type="checkbox"/> Dewatering <input type="checkbox"/> Other (Specify below) <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Industrial <input type="checkbox"/> Domestic-lawn & garden <input type="checkbox"/> Monitoring well Was a chemical/bacteriological sample submitted to Department? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, mo/day/yr sample was submitted _____ Water well disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No																																																																									
5 TYPE OF CASING USED: <input type="checkbox"/> Steel <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Other _____ CASING JOINTS: <input checked="" type="checkbox"/> Glued <input type="checkbox"/> Clamped <input type="checkbox"/> Welded <input type="checkbox"/> Threaded Casing diameter 16 in. to 68 ft., Diameter 16 in. to 84 ft., Diameter 16 in. to 94 ft. Casing height above land surface 12 in., Weight 19.75 lbs./ft., Wall thickness or gauge No. .616 TYPE OF SCREEN OR PERFORATION MATERIAL: <input type="checkbox"/> Steel <input checked="" type="checkbox"/> Stainless Steel <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Other (Specify) _____ <input type="checkbox"/> Brass <input type="checkbox"/> Galvanized Steel <input type="checkbox"/> None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: <input type="checkbox"/> Continuous slot <input checked="" type="checkbox"/> Mill slot <input type="checkbox"/> Gauze wrapped <input type="checkbox"/> Torch cut <input type="checkbox"/> Drilled holes <input type="checkbox"/> None (open hole) <input type="checkbox"/> Louvered shutter <input type="checkbox"/> Key punched <input checked="" type="checkbox"/> Wire wrapped <input type="checkbox"/> Saw cut <input type="checkbox"/> Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 68 ft. to 76 ft., From 84 ft. to 87 ft. From 94 ft. to 108 ft., From 108 ft. to 113 ft. GRAVEL PACK INTERVALS: From 22 ft. to 114 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																											
6 GROUT MATERIAL: <input type="checkbox"/> Neat cement <input type="checkbox"/> Cement grout <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Other _____ Grout Intervals: From 2 ft. to 22 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: <input type="checkbox"/> Septic tank <input type="checkbox"/> Lateral lines <input type="checkbox"/> Pit privy <input type="checkbox"/> Livestock pens <input type="checkbox"/> Insecticide storage <input checked="" type="checkbox"/> Other (specify below) <input type="checkbox"/> Sewer lines <input type="checkbox"/> Cesspool <input type="checkbox"/> Sewage lagoon <input type="checkbox"/> Fuel storage <input type="checkbox"/> Abandoned water well <input type="checkbox"/> Watertight sewer lines <input type="checkbox"/> Seepage pit <input type="checkbox"/> Feedyard <input type="checkbox"/> Fertilizer storage <input type="checkbox"/> Oil well/gas well None Known Direction from well _____ Distance from well _____																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>2</td> <td>Topsoil</td> <td>76</td> <td>84</td> <td>Clay, gray, yellow</td> </tr> <tr> <td>2</td> <td>4</td> <td>Clay, tan</td> <td>84</td> <td>87</td> <td>Sand, gravel, fine to medium</td> </tr> <tr> <td>4</td> <td>6</td> <td>Sand, fine</td> <td>87</td> <td>92</td> <td>Clay, gray</td> </tr> <tr> <td>6</td> <td>20</td> <td>Sand, fine, silty brown clay</td> <td>92</td> <td>94</td> <td>Clay, yellow, tan, caliche</td> </tr> <tr> <td>20</td> <td>22</td> <td>Clay, tan, soft</td> <td>94</td> <td>113</td> <td>Sand & gravel, fine to coarse</td> </tr> <tr> <td>22</td> <td>42</td> <td>Sand, fine to coarse, clay streaks</td> <td>113</td> <td>114</td> <td>Clay, gray</td> </tr> <tr> <td>42</td> <td>44</td> <td>Clay, yellow</td> <td></td> <td></td> <td></td> </tr> <tr> <td>44</td> <td>65</td> <td>Sand & gravel, fine to coarse, clay streak</td> <td></td> <td></td> <td></td> </tr> <tr> <td>65</td> <td>68</td> <td>Clay, yellow</td> <td></td> <td></td> <td></td> </tr> <tr> <td>68</td> <td>76</td> <td>Sand, gravel, fine to coarse</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	2	Topsoil	76	84	Clay, gray, yellow	2	4	Clay, tan	84	87	Sand, gravel, fine to medium	4	6	Sand, fine	87	92	Clay, gray	6	20	Sand, fine, silty brown clay	92	94	Clay, yellow, tan, caliche	20	22	Clay, tan, soft	94	113	Sand & gravel, fine to coarse	22	42	Sand, fine to coarse, clay streaks	113	114	Clay, gray	42	44	Clay, yellow				44	65	Sand & gravel, fine to coarse, clay streak				65	68	Clay, yellow				68	76	Sand, gravel, fine to coarse			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	2	Topsoil	76	84	Clay, gray, yellow																																																																						
2	4	Clay, tan	84	87	Sand, gravel, fine to medium																																																																						
4	6	Sand, fine	87	92	Clay, gray																																																																						
6	20	Sand, fine, silty brown clay	92	94	Clay, yellow, tan, caliche																																																																						
20	22	Clay, tan, soft	94	113	Sand & gravel, fine to coarse																																																																						
22	42	Sand, fine to coarse, clay streaks	113	114	Clay, gray																																																																						
42	44	Clay, yellow																																																																									
44	65	Sand & gravel, fine to coarse, clay streak																																																																									
65	68	Clay, yellow																																																																									
68	76	Sand, gravel, fine to coarse																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <input checked="" type="checkbox"/> constructed, <input type="checkbox"/> reconstructed, or <input type="checkbox"/> plugged under my jurisdiction and was completed on (mo/day/year) 01/03/13 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 01/07/13 under the business name of Clarke Well & Equipment, Inc. by (signature) _____																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											