

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

County	Fraction	Section number	Township number	Range number
Pawnee	nw 1/4 SE 1/4 SE 1/4	3	T 22 S	R 17 E

  

2. Distance and direction from nearest town or city: 1 1/2 s.w. 2 1/2 w. of Larned, Ks. Street address of well location if in city: North side of rd.	3. Owner of well: Joe Lewis R.R. or street: Rt. #3 City, state, zip code: Larned Kansas
---	---

  

4. Locate with "X" in section below:  Sketch map:	6. Bore hole dia. 9 in. Completion date 9-29-76 Well depth 100 ft.
	7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
	9. Casing: Material pvc Height: Above or below surface 18 in. Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> RMP PVC Weight 160 lbs./ft. Dia. 5 1/2 in. to 100 ft. depth Wall Thickness: inches 25 Dia. in. to ft. depth gage No.

  

5. Type and color of material	From	To	
Top Soil	0	2	
Brown Clay	2	16	
Blue Clay	16	29	
Sand & Gravel	29	47	
Fine sand & blue clay mix	47	51	
Brown Clay	51	64	
Sand & Gravel	64	90	
Sand & Gravel brown clay mix	90	100	

  

10. Screen: Manufacturer's name Peerless Type pvc Dia. 5 1/2 Slot/gauge 1/16 Length 20' Set between 80 ft. and 100 ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/2 3/4	11. Static water level: mo./day/yr. 14 ft. below land surface Date 9-29-76 12. Pumping level below land surfaces: NA ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
13. Water sample submitted: mo./day/yr. X Yes No Date 9-29-76	14. Well head completion: Pitless adapter 18 inches above grade
15. Well grouted? YES With: X Neat cement Bentonite Concrete Depth: From 0 ft. to 10 ft.	16. Nearest source of possible contamination: ft. 300 Direction East Type Barn Yard Well disinfected upon completion? X Yes No
17. Pump: XX Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: Submersible Turbine Jet Reciprocating Centrifugal Other	

(Use a second sheet if needed)

  

18. Elevation:	19. Remarks:	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosecrantz - Bemis 134 Business name License No. Address Great Bend, Ks. Signed Sandy Hilgert Date 8/8/76 Authorized Representative
----------------	--------------	--

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

MI-1023