

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Pawnee</b>	Fraction <b>1/4 NE 1/4 NW 1/4</b>	Section number <b>10</b>	Township number <b>T 22 S</b>	Range number <b>R 17 E/W</b>
2. Distance and direction from nearest town or city: <b>1 1/2 SW 2 3/4 W of Larned</b> Street address of well location if in city:				3. Owner of well: <b>Lewis</b> R.R. or street: City, state, zip code: <b>Larned, Ks.</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>9</b> in. Completion date <b>9-27-76</b> Well depth <b>92</b> ft.		
				7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
				8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
5. Type and color of material		From To		9. Casing: Material <input type="checkbox"/> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <b>5 1/2</b> PVC <input checked="" type="checkbox"/> Weight <b>160</b> lbs./ft. Dia. <b>5 1/2</b> in. to <b>92</b> ft. depth Wall Thickness: inches or Dia. <b>5 1/2</b> in. to <b>92</b> ft. depth gage No. <b>1214</b>		
				10. Screen: Manufacturer's name <b>R/B Peerless</b> Type <b>PVC</b> Dia. <b>5 1/2</b> Slot/groove <b>1/16</b> Length <b>20</b> Set between <b>72</b> ft. and <b>92</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/2 3/4</b>		
Top soil		0 2		11. Static water level: <b>15</b> ft. below land surface Date <b>9-27-76</b> mo./day/yr.		
Brown clay		2 13		12. Pumping level below land surfaces: <b>NA</b> ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.		
Sand & gravel		13 31		13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <b>9-27-76</b> mo./day/yr.		
Gray Sand & gravel		31 41		14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter ____ inches above grade		
Gray & brown clay		41 46		15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.		
Brown clay some gravel		46 48		16. Nearest source of possible contamination: ft. <b>300</b> Direction <b>South</b> Type <b>Barn Yard</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Brown clay with fine sand		48 71		17. Pump: <input checked="" type="checkbox"/> Not installed		
Sand & gravel		71 92		Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Rosencrantz-Bemis 134</b> Business name _____ License No. _____ Address <b>Great Bend, Ks.</b> Signed <b>Fredrick Anderson</b> Date <b>9/27/76</b> Authorized representative		
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5