

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: <u>Pawnee</u>		SE 1/4 SW 1/4 SW 1/4		19		T 22 S		R 19 E/W	
Distance and direction from nearest town or city street address of well if located within city?									
<u>5 south, 2 3/4 west of Rozel, Ks.</u>									
2 WATER WELL OWNER:		John Price							
RR#, St. Address, Box # :		Rt. 1-Box 2							
City, State, ZIP Code :		Rozel, Ks. 67574							
		Board of Agriculture, Division of Water Resources Application Number: <u>17508</u>							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>217</u> ft. ELEVATION: _____							
		Depth(s) Groundwater Encountered 1. _____ ft. 2. _____ ft. 3. _____ ft.							
		WELL'S STATIC WATER LEVEL <u>39</u> ft. below land surface measured on <u>mo/day/yr</u> <u>8-17-98</u>							
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm							
		Est. Yield <u>1000</u> gpm: Well water was <u>174</u> ft. after <u>3 1/2</u> hours pumping <u>800</u> gpm							
		Bore Hole Diameter <u>28</u> in. to <u>21.7</u> in. to _____ in. to _____ in.							
		WELL WATER TO BE USED AS:							
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) <u>2 Irrigation</u> 4 Industrial 7 Lawn and garden only 10 Monitoring well							
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No <u>X</u> ; If yes, mo/day/yr sample was submitted _____							
		Water Well Disinfected? Yes _____ No <u>X</u>							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <u>X</u> Clamped _____							
1 Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded _____							
2 PVC 4 ABS		7 Fiberglass _____ Threaded _____							
Blank casing diameter <u>16</u> in. to <u>15.7</u> ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.									
Casing height above land surface <u>12</u> in., weight <u>SDR 32.5</u> lbs./ft. Wall thickness or gauge No. _____									
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement							
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) _____									
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)							
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes									
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) _____									
SCREEN-PERFORATED INTERVALS: From <u>15.7</u> ft. to <u>217</u> ft., From _____ ft. to _____ ft.									
		From _____ ft. to _____ ft., From _____ ft. to _____ ft.							
GRAVEL PACK INTERVALS: From <u>217</u> ft. to <u>20</u> ft., From _____ ft. to _____ ft.									
		From _____ ft. to _____ ft., From _____ ft. to _____ ft.							
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other _____							
Grout Intervals: From <u>20</u> ft. to <u>0</u> ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.									
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well							
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage									
Direction from well? <u>south</u>		How many feet? <u>40'</u>							
FROM	TO	LITHOLOGIC LOG		FROM	TO	PLUGGING INTERVALS			
0	2	Top soil		193	200	Dark blue shale			
2	13	Brown clay		200	217	Sand rock			
13	32	Brown & white clay							
32	45	Red fire clay							
45	61	Yellow brown, gray gritty fire clay							
61	66	Sand rock							
66	68	Yellow brown, gray gritty clay							
68	74	Red fire clay							
74	80	Light gray clay							
80	90	Coal, sandy shale & fire clay							
90	95	Sandy light gray clay & sand streaks							
95	99	Sand rock							
99	120	Blue gray shale							
120	133	Coal, iron pyrite sand rock & shale							
133	193	Sand rock- drilled good							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>8-22-98</u> and this record is true to the best of my knowledge and belief. Kansas									
Water Well Contractor's License No. <u>134</u> This Water Well Record was completed on (mo/day/yr) <u>9-9-98</u>									
under the business name of <u>Rosencrantz-Bemis</u> by (signature) <u>Freddie Dodson</u>									