

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Pawnee</u>	Fraction <u>NW 1/4 NE 1/4 SE 1/4</u>	Section number <u>2</u>	Township number T <u>22</u> S R <u>19</u> E/W
2. Distance and direction from nearest town or city: <u>2 mi. E of Rozel 1 1/2 S west into field</u> Street address of well location if in city:			3. Owner of well: <u>Allen Klein</u> R.R. or street: City, state, zip code: <u>Rozel, Ks. 67574</u>		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>29</u> in. Completion date <u>3-23-77</u> Well depth <u>108</u> ft.	
5. Type and color of material		From	To	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
Top Soil		0	4	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Light Brown Clay		4	42	9. Casing: Material <u>steel</u> Height: Above or <u>below</u> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>108</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>7</u>	
Fine Sand		12	45	10. Screen: Manufacturer's name <u>Doeris & Cook</u> Type <u>steel</u> Dia. <u>16</u> Slot/gauge <u>3/16</u> Length <u>33</u> Set between <u>75</u> ft. and <u>108</u> ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>3/4 1/2 3/8</u>	
Gray Brown Clay W/Sand		45	51 1/2	11. Static water level: <u>56</u> ft. below land surface Date <u>1-5-77</u> mo./day/yr.	
Sand and Gravel clean loose		51 1/2	74	12. Pumping level below land surfaces: <u>72</u> ft. after <u>1</u> hrs. pumping <u>700</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>800</u> g.p.m.	
Brown Clay & Sand		74	77	13. Water sample submitted: <u> </u> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <u>1-5-77</u>	
Sand and Gravel clean loose		77	80	14. Well head completion: <u> </u> Pitless adapter <u> </u> Inches above grade	
Brown Clay some Gravel		80	85	15. Well grouted? <u>yes</u> With: <u> </u> Neat cement <u> </u> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
Fine Sand some Clay		85	95	16. Nearest source of possible contamination: ft. <u>4m</u> Direction <u>N</u> Type <u>sewer</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Good clean loose Sand & Gravel		95	108	17. Pump: <u> </u> Not installed Manufacturer's name <u>Western Land Roller</u> Model number <u>2BHC12</u> HP <u>30</u> Volts <u> </u> Length of drop pipe <u>100</u> ft. capacity <u>800</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Brown Clay Fine Sand Mixed		108	116	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz-Bemis 134</u> Business name <u>Great Bend, Ks.</u> License No. <u> </u> Address <u> </u> Signed <u>Sander K. Rose</u> Date <u>5-9-77</u> Authorized representative	
Sand & Gravel coarse		116	120		
Fire Clay		120	125		
(Use a second sheet if needed)					
18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks:			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5