

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Harvey</u>	<u>NW 1/4 NW 1/4 NE 1/4</u>	<u>7</u>	T <u>22</u> S	R <u>2</u> E <u>W</u>

Distance and direction from nearest town or city street address of well if located within city?

3 mi S, 3 1/2 W of Moundridge

2 WATER WELL OWNER:	RR#, St. Address, Box # :	Board of Agriculture, Division of Water Resources
City, State, ZIP Code :	<u>Moundridge, KS 67107</u>	Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: <u>102</u> ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL <u>42</u> ft. below land surface measured on mo/day/yr <u>7-23-91</u> Pump test data: Well water was <u>49</u> ft. after <u>1</u> hours pumping <u>20</u> gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter <u>8</u> in. to <u>105</u> ft. and in. to ft. WELL WATER TO BE USED AS: ☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes <u>X</u> No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
☒ PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter <u>5</u> in. to <u>92</u> ft. Dia			Threaded
Casing height above land surface <u>12</u> in. weight <u>2.37</u> lbs./ft. Wall thickness or gauge No. <u>160</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL:	☒ PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	☒ Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From <u>92</u> ft. to <u>102</u> ft.	From ft. to ft.	
	From ft. to ft.	From ft. to ft.	
GRAVEL PACK INTERVALS:	From <u>23</u> ft. to <u>55</u> ft.	From ft. to ft.	
	From <u>60</u> ft. to <u>105</u> ft.	From ft. to ft.	

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	☒ Bentonite	4 Other
Grout Intervals: From <u>3</u> ft. to <u>23</u> ft.	From <u>55</u> ft. to <u>60</u> ft.	From ft. to ft.	From ft. to ft.	
What is the nearest source of possible contamination:	10 Livestock pens	14 Abandoned water well		
1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well
2 Sewer lines	5 Cess pool	☒ Sewage lagoon	12 Fertilizer storage	16 Other (specify below)
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage	
Direction from well? <u>S</u>		How many feet? <u>150</u>		

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
<u>0</u>	<u>19</u>	<u>Br clay</u>			
<u>19</u>	<u>22</u>	<u>F Sand</u>			
<u>22</u>	<u>70 1/2</u>	<u>Gray clay</u>			
<u>70</u>	<u>104</u>	<u>sand + sm Gravel</u>			
<u>104</u>	<u>105</u>	<u>Shale</u>			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>7-23-91</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>447</u> This Water Well Record was completed on (mo/day/yr) <u>2-21-92</u> under the business name of <u>Miller Drilling</u> by (signature) <u>[Signature]</u>
--