

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Harvey		NE 1/4 NW 1/4 NE 1/4		25		T 22 S		R 2 E W	
Distance and direction from nearest town or city street address of well if located within city? Approximately 2 1/4 miles west and 2 miles south of Hesston									
2 WATER WELL OWNER: Harvey County RWD #1 RR#, St. Address, Box # : 107 N. Walnut - P.O. Box 124 City, State, ZIP Code : Peabody, KS 66866 Board of Agriculture, Division of Water Resources Application Number:									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 97 ft. ELEVATION: unknown							
		Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 16.04 ft. below land surface measured on mo/day/yr 8-18-04 Pump test data: Well water was not checked ft. after hours pumping gpm Est. Yield unknown gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 5 in. to 100 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 11 Injection well 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well 12 Other (specify below) Observation Well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒							
		5 TYPE OF BLANK CASING USED:							
		1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded							
		Blank casing diameter 2 in. to 65 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 24 in., weight .44 lbs./ft. Wall thickness or gauge No .091							
		TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:									
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 10 Other (specify) ft. 7 Torch cut 10 Other (specify) ft.									
SCREEN-PERFORATED INTERVALS: From 65 ft. to 95 ft., From ft. to ft.									
GRAVEL PACK INTERVALS: From 40 ft. to 100 ft., From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug									
Grout Intervals: From ft. to ft., From ft. to ft., From 0 ft. to 40 ft.									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) None known									
Direction from well? How many feet?									
FROM	TO	LITHOLOGIC LOG		FROM	TO	PLUGGING INTERVALS			
0	5	Topsoil							
5	8	Clay, brown							
8	14	Clay, tan							
14	18	Clay, tannish gray							
18	39	Clay, tan, sandy, hard							
39	50	Sand, coarse to fine							
50	61	Sand and gravel, coarse to fine, clay streak at 56'							
61	65	Clay, brown and gravel streaks							
65	73	Sand and gravel, coarse to fine							
73	75	Clay, brown							
75	95	Sand and gravel, coarse to fine							
95	100	Shale, gray, green							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-18-04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 8-24-04 under the business name of Clarke Well & Equipment, Inc. by (signature)									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.									

RECEIVED

AUG 26 2004

BUREAU OF WATER