

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

Location listed as:

Section-Township-Range: None Given

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): _____

County: Harvey

Location changed to:

15-225-2W

N2 N2 NW NW NE

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: Written description, locations of well #8 and
Test Hole #2, and aerial photos on KGS mapping tool
online initials: DRL date: 6/6/2006

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

SALINA, KANSAS
Box 477

LOG OF WELL

NAME Hesston Cit HOLE NO. 2 DATE DRILLED Feb. 13, 1962
LOCATION 700 ft. N. of City well No. 6 T , R , Co.
TYPE OF WELL Test hole TOPOGRAPHY upland flat
DEPTH 142 FEET. DIAM. OF HOLE 4 1/2 INCHES. DEPTH TO WATER FEET
CASINGS
YIELD
REMARKS Same Location as our Test Hole # 2

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
Clay, silty, dark gray and gray	4	4	
Clay, silty, tan	7	11	
Clay, silty, sandy, gray-white and light buff	36	47	
Sand, coarse to fine, some gravel, coarse	9	56	High permeability
Silt, soft, sandy, buff	11	67	
Gravel, fine to medium and sand	9	76	
Clay, buff, compact	7.5	83.5	
Sand, coarse to fine	9.5	93	
Gravel, fine to medium and sand	4	97	
Clay, compact, blue-gray and light gray, sandy	7	104	
Sand, fine to coarse	6	110	
Gravel, fine to medium and sand	7	117	High permeability
Gravel, medium to fine, sand, and silt, tan	4	121	
Gravel, medium to fine and sand, few pebbles thin clay at 125	6	127	High permeability
Gravel, medium to fine and sand, and clay, tan, few pebbles and cobbles	7	134	
Permian:			
Shale, blue-gray; contains calcite seams	8	142	