

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HODGENAN SE 1/4 SE 1/4 SW 1/4 4 T 22 S R 23 EW (DRL)

Distance and direction from nearest town or city street address of well if located within city?
 FROM JETMORE N. ON 283 TO RD. 0 -2E. ON 220 1N. TO RD R 1/2E

2 WATER WELL OWNER: BRADSHAW, WILBURN Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: 3095 W.E. R RD. Application Number:
 City, State, ZIP code: JETMORE, KS 67854-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 505 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 176 ft. below land surface measured on mo/day/yr 09/28/10
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 505 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 505 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17 + Sch 20
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 420 ft. to 500 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 505 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	01 TOPSOIL			
10	30	32 TAN CLAY			
30	50	32 TAN CLAY 16 GRAY CLAY			
50	240	07 BLUE SHALE 08 ROCK LAYERS			
240	260	16 GRAY CLAY			
260	320	16 GRAY CLAY 26 RED CLAY 29 SANDSTONE			
320	510	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/29/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/06/10 under the business name of JOE'S WELL SERVICE, INC. by (signature) Judith Crick