

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

JETMORE NW

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

CDB

1. Location of well:		County Hodgeman	Fraction NW¹/₄ SE¹/₄ SW¹/₄	Section number 3	Township number T 22	Range number S R 24	E/W
2. Distance and direction from nearest town or city: 5 mi north-3 mi west of Jetmore Street address of well location if in city:				3. Owner of well: Alex Dechant R.R. or street: Bazine Rte #1 City, state, zip code: Ks. 67516			
4. Locate with "X" in section below:			Sketch map:		6. Bore hole dig. 24 in. Completion date Well depth 577 ft. 4-19-78		
					7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material			From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Clay			0	20	9. Casing: Material Steel Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 36.86 lbs./ft. Dia. 16 in. to 577 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. .219		
Sand, gravel			20	(80)	10. Screen: Manufacturer's name Lakewood Type Millslot Dia. 16 Slot/gauze 1/8x2 Length 124 Set between 453 ft. and 577 ft. <input type="checkbox"/> Yes <input type="checkbox"/> No ft. and <input type="checkbox"/> ft. Gravel pack? <input type="checkbox"/> Size range of material 3/4		
Clay			80	100	11. Static water level: <input type="checkbox"/> mo./day/yr. 110 ft. below land surface Date 6-10-76		
Shale, clay			100	400	12. Pumping level below land surfaces: 567 ft. after 10 hrs. pumping 450 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 450 g.p.m.		
Clay, trace sand, fine			400	500	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date		
Sand, clean			500	520	14. Well head completion: 12 inches above grade <input type="checkbox"/> Pitless adapter		
Sand rock			520	575	15. Well grouted? Yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
Shale			575	577	16. Nearest source of possible contamination: NA ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
BROCK 80' pm					17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Worthington Model number 11S-12M-75 Volts <input type="checkbox"/> Length of drop pipe 550 ft. capacity 450 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
CRETACEOUS WELL					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 136A High Plains Drilling & Supply, Inc. Business name High Plains Drilling & Supply, Inc. License No. <input type="checkbox"/> Address 402 N 3rd, Garden City, KS. Signed Be D. Harkness Date 5-17-78 Authorized representative		
(Use a second sheet if needed)							
18. Elevation:		19. Remarks:					
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		TOPO 2452 80 2472					

22 240 - 3 NW SE SW
1/4 1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5