

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HODGENAN SE 1/4 SE 1/4 NE 1/4 34 T 22 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JETHORE - 2 WEST, 1/2 NORTH ON 156 HIGHWAY

WATER WELL OWNER: TARNAN, JOE
 RR#, St. Address, Box #: RR #2 -- BOX 113 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JETHORE, KS 67854- Application Number:

LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 455 ELEVATION: 0
 N "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

NW	NE
SW	SE

WELL'S STATIC WATER LEVEL 185 ft. below land surface measured on no/day/yr 01/15/99
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 455 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 455 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 370 ft. to 450 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 455 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

ROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? EAST How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY YELLOW CLAY			
20	40	YELLOW CLAY			
40	60	YELLOW CLAY BLUE SHALE			
60	200	BLUE SHALE THIN ROCK LAYER			
200	220	BLUE CLAY			
220	240	BLUE SHALE SANDSTONE CLAY LAYERS			
240	250	BLUE SHALE			
250	320	SANDSTONE			
320	360	SANDSTONE BLUE CLAY			
360	460	SANDSTONE			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 01/16/99 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 02/04/99 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*

Continued) WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HODGENAN SE 1/4 SE 1/4 NE 1/4 34 T 22 S R 24 W

WATER WELL OWNER: TARNAN, JOE
 RR#, St. Address, Box #: RR #2 -- BOX 113 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JETHORE, KS 67854- Application Number:

FROM TO LITHOLOGIC LOG
 460 480 SANDSTONE CLAY LAYERS