

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Harvey</u>	<u>ne 1/4 ne 1/4 ne 1/4</u>	<u>21</u>	<u>T 22 S</u>	<u>R 3</u> EW

Distance and direction from nearest town or city street address of well if located within city?

7 north 1 east of Burrton, Ks.

2 WATER WELL OWNER:	<u>Allen Drilling</u>	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	<u>Box 1389</u>	Application Number: <u>T87-458</u>
City, State, ZIP Code :	<u>Great Bend, Ks.</u>	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL... <u>110</u> ... ft. ELEVATION:
--	--

Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL .. 24... ft. below land surface measured on mo/day/yr 10-27-87.....

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield .. na... gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter .. 10... in. to 110... ft., and in. to ft.

WELL WATER TO BE USED AS:

1 Domestic	3 Feedlot	6 Oil field water supply	8 Air conditioning	11 Injection well
2 Irrigation	4 Industrial	7 Lawn and garden only	9 Dewatering	12 Other (Specify below)
10 Observation well				

Was a chemical/bacteriological sample submitted to Department? Yes.....No...X.....; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes hth No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ... <u>X</u> ... Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
<u>2 PVC</u>	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter <u>5</u> ... in. to <u>80</u> ... ft., Dia	11 Other (specify)	12 None used (open hole)	
Casing height above land surface <u>24</u> ... in., weight	13 Other (specify)		
TYPE OF SCREEN OR PERFORATION MATERIAL:	14 Other (specify)		
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	10 Asbestos-cement		
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
SCREEN-PERFORATED INTERVALS:	7 Torch cut	10 Other (specify)	
From <u>80</u> ... ft. to <u>110</u> ... ft., From			
GRAVEL PACK INTERVALS:			
From <u>20</u> ... ft. to <u>110</u> ... ft., From			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From <u>0</u> ... ft. to <u>20</u> ... ft., From				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well?	<u>south east</u>	How many feet?	<u>130</u>	

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	3	Top soil			
3	21	Brown clay			
21	58	White and brown clay			
58	80	Sand and gravel			
80	90	Sand and clay mixed			
90	105	Sand and gravel			
105	110	Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>10-27-87</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>134</u> This Water Well Record was completed on (mo/day/yr) .. <u>11-4-87</u> under the business name of <u>Roencrantz-Bemis</u> by (signature) <u>Walter H. Adams</u>
--

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Office of Oil Field and Environmental Geology, Regulation and Permitting Section, Topeka, Kansas 66620-7500, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.