


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County <u>Forney</u>	Township name <u>Alta</u>	Fraction <u>Center 7</u> <u>NE 1/4 - NW 1/4</u>	Section number <u>33</u>	Town number <u>T22 S</u>	Range number <u>R-3-W</u>
Distance and direction from nearest town or city: <u>13 West 3 South</u>			3 Owner of well: <u>James Graber</u>			
Street address of well location if in city: <u>Harston Kans.</u>			Address: <u>Moundridge Kans.</u>			
Locate with "X" in section below:		Sketch map:		4 Well depth: <u>143</u> ft. Date of completion: <u>3-25-75</u> Well diameter <u>30</u> in.		
		<u>Irreg Type Well</u> <u>Center of 2-1/4 Sec. for</u> <u>Fish Ponds & Wildlife</u>		5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
2		Type and color of material	From	To	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>	
		<u>Loose dry sand</u>	<u>0</u>	<u>6</u>	7 Casing: Material <u>Iron</u> Height: <u>above</u> below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>12</u> in. Diam. <u>16</u> in. to <u>143</u> ft. depth Drive shoe? <input type="checkbox"/> Yes <input type="checkbox"/> No <u>16</u> in. to <u>143</u> ft. depth	
		<u>dark clays</u>	<u>6</u>	<u>9</u>	8 Screen: <u>Purco Tilo Co.</u> Manufacture <u>Transita</u> Dia. <u>16" I.D.</u> Slot/gauze <u>38</u> Length <u>59</u> Set between <u>42</u> ft. and <u>112</u> ft. Fittings: <u>42-55</u> <u>1/8"-1/4"</u> Gravel pack <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No Size range of material <u> </u>	
		<u>Silty clays</u>	<u>9</u>	<u>42</u>	9 Static water level: <u>13</u> ft. below land surface Date <u>3-25-75</u>	
		<u>Med to coarse sand & gravel</u>	<u>42</u>	<u>67</u>	10 Pumping level below land surfaces: <u>50</u> ft. after <u>2</u> hrs. pumping <u>1200</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>2000</u> g.p.m.	
		<u>Buff clays</u>	<u>67</u>	<u>79</u>	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>	
		<u>Med sand</u>	<u>79</u>	<u>92</u>	12 Well head completion: <input type="checkbox"/> Pitless adapter <u>12"</u> Inches above grade	
		<u>Black mud</u>	<u>92</u>	<u>110</u>	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <u>clays</u> Depth: From <u>0</u> ft. to <u>20</u> ft.	
		<u>Med coarse sand</u>	<u>110</u>	<u>143</u>	14 Nearest source of possible contamination: ft. <u>None</u> Direction <u>Land Hill Pasture</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
		<u>some coarse layers</u>			15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <u>Victor Sand Pumps</u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
16 Remarks: elevation		17 Water well contractor's certification:				
<u>Well top of sandy slope Hill</u>		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.				
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		Business name <u>Peterson Bros INC</u> License No. <u>138</u> Address <u>Box 150 Lindsay Kans</u> Signed <u>Warren Peterson</u> Date <u>3-26-75</u> By <u>JP</u> Authorized representative				