

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SW 1/4 SE 1/4 SE 1/4	04	T 22 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?

FROM GARDEN CITY; APPX 2 MILES WEST & 11 3/4 MILES NORTH

2 WATER WELL OWNER:	CRAIG ADAM	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	4715 W. TENNIS ROAD	Application Number: 18888
City, State, ZIP code :	GARDEN CITY, KS 67846-	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 223 ELEVATION: 0
<div style="display: flex; justify-content: space-around;"> <div> <p>Depth(s) Groundwater Encountered</p> <p>1. 0 ft. 2. 0 ft. 3. 0 ft.</p> </div> <div> <p>WELL'S STATIC WATER LEVEL 114 ft. below land surface measured on mo/day/yr 05/14/07</p> <p>Pump test data: Well water was 152 ft. after 4 hours pumping 833 gpm</p> <p>Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm</p> </div> </div>	
<div style="display: flex; justify-content: space-around;"> <div> <p>Bore Hole Diameter 24 in. to 223 ft., and in. to 0 ft.</p> <p>WELL WATER TO BE USED AS: 02 IRRIGATION</p> <p>Was a chemical/bacteriological sample submitted to department? No ;</p> <p>If yes, mo/day/yr sample was submitted Water well disinfected? Yes</p> </div> <div> <p>Diagram showing section box with 'X' in the SW corner.</p> </div> </div>	

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
Blank casing diameter 16 in. to 223 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219	
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL	
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT	
SCREEN PERFORATED INTERVALS:	From 133 ft. to 213 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 223 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? WEST
How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	20	01 CLAY 07 FINE SAND			
20	44	01 CLAY			
44	54	01 CLAY 20 LIMESTONE			
54	62	07 FINE SAND 08 MEDIUM SAND			
62	93	01 CLAY 05 SAND			
93	115	01 CLAY 20 LIMESTONE			
115	136	05 SAND			
136	156	05 SAND 13 FINE GRAVEL 28 ROCK			
156	160	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/11/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/28/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SW 1/4 SE 1/4 SE 1/4	04	T 22 S	R 33 W

2 WATER WELL OWNER: CRAIG ADAM

RR#, St. Address, Box # : 4715 W. TENNIS ROAD

Board of Agriculture, Division of Water Resources

City, State, ZIP code : GARDEN CITY, KS 67846-

Application Number: 18888

FROM	TO	LITHOLOGIC LOG
160	175	07 FINE SAND 08 MEDIUM SAND
175	195	28 ROCK 01 CLAY 05 SAND
195	199	31 CALICHE
199	213	31 CALICHE 23 SANDSTONE
213	220	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/11/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/28/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Brian J. Burkhardt