

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY NE 1/4 NW 1/4 NE 1/4 36 T 22 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM DEERFIELD; APPX 6 1/2 MILES NORTH & 3/4 MILES EAST

2 WATER WELL OWNER: FRANK EBERHART Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: RR 1 BOX 280 Application Number: 2651 & 8393  
 City, State, ZIP code: DEERFIELD, KS 67838-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \		X			
1	--- NW ---	---	NE ---	---	
M					
i	W ---	---	---	E ---	
l					
e	---	---	---	---	
\ /	---	---	---	---	

4 DEPTH OF COMPLETED WELL 248 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 166 ft. below land surface measured on mo/day/yr 06/03/05  
 Pump test data: Well water was 197 ft. after 4 hours pumping 700 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 248 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 248 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 190 ft. to 230 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 248 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? EAST How many feet? 125

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	12	04 SANDY CLAY			
12	17	07 FINE SAND			
17	36	05 SAND 13 FINE GRAVEL			
36	56	04 SANDY CLAY			
56	67	05 SAND 13 FINE GRAVEL			
67	90	04 SANDY CLAY			
90	107	05 SAND 13 FINE GRAVEL			
107	119	04 SANDY CLAY 20 LIMESTONE			
119	125	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 05/28/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/10/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 047 KEARNY	Fraction NE 1/4 NW 1/4 NE 1/4	Section Number 36	Township Number T 22 S	Range Number R 35 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	FRANK EBERHART RR 1 BOX 280 DEERFIELD, KS 67838-	Board of Agriculture, Division of Water Resources Application Number: 2651 & 8393
---	--	--

FROM	TO	LITHOLOGIC LOG
125	130	04 SANDY CLAY
130	148	05 SAND 13 FINE GRAVEL
148	156	04 SANDY CLAY
156	163	05 SAND 13 FINE GRAVEL
163	167	04 SANDY CLAY
167	181	05 SAND 13 FINE GRAVEL
181	190	04 SANDY CLAY
190	200	05 SAND 13 FINE GRAVEL
200	208	07 FINE SAND
208	228	05 SAND 28 ROCK
228	235	31 CALICHE
235	260	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/28/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/10/05 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Frank Eberhart*