

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: ; Fraction ; Section Number ; Township Number ; Range Number
 COUNTY: 047 KEARNEY ; NW 1/4 SW 1/4 NW 1/4 ; 22 ; T 22 S ; R 36 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 12 3/4 MILES NORTH OF LAKIN.

2 WATER WELL OWNER: DIENST, INC.
 RR#, St. Address, Box #: P.O. BOX 207 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LAKIN, KS 67860- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: ; 4 DEPTH OF COMPLETED WELL 195 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 150 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 150 ft. below land surface measured on mo/day/yr 09/13/91
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9.875 in. to 195 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: BLUED
 Blank casing diameter 5 in. to 195 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 145 ft. to 195 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 195 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 260

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	11	01 CLAY			
11	26	31 CALICHE			
26	104	08 MEDIUM SAND 01 CLAY 23 SANDSTONE			
104	141	04 SANDY CLAY 05 SAND			
141	152	08 MEDIUM SAND 01 CLAY 23 SANDSTONE			
152	157	04 SANDY CLAY 05 SAND			
157	166	08 MEDIUM SAND 14 MED GRAVEL 28 ROCK			
166	182	04 SANDY CLAY 05 SAND			
182	192	07 FINE SAND 08 MEDIUM SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/14/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/05/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas R. Henkle*

