

LOG OF DATA

(FIELD COPIES OF DRILLERS LOGS)

STATE _____ COUNTY Kearny NUMBER 21ddLOCATION SE 1/4 SE 1/4 SEC. 31, T. 22 R. 36DRILLER XSGS ADDRESS 21ddSOURCE OF DATA Obs & samples
(APPEND CASING RECORD AND ADDITIONAL DATA ON NOTE SHEET)E 3217

DRILLER'S DESCRIPTION

THICKNESS DEPTH

surface soil	3	3
silty top hard	12	15
Caliche white clay sandy		
Very hard turning brown	8	23
Sand cemented brown hard	4	27
Caliche Brown hard	9	36
silt brown sandy	2	38
Sand fine ^{to med} drilled easy ^{70% fine}	5	43
Sand fine to coarse cemented		
drilled hard 50% fine	12	55
Sand fine to coarse as above		
loose, drilled easy	10	65
as above only cemented tight hard	4	69
hard loose drilled easy	4	73

PAGE _____ OF _____ PAGES

LOG OF WELL
(FOR FILED COPIES OF DRILLERS LOGS)

STATE _____ COUNTY _____ NUMBER _____

LOCATION _____ S. _____ T. _____ R. _____

OWNER _____ ADDRESS _____

SOURCE OF DATA
(APPEND CASING RECORD AND ADDITIONAL DATA ON HOPE SHEET)

DRILLER'S DESCRIPTION	THICKNESS	DEPTH
Sand fine to coarse drilled medium	5	73
sand & gravel caliche cemented		78
drilled ——— hard	8	86
Sand fine to coarse gravel		
drilled Medium	9	95
Gravel med to coarse		
cut jumped good	4	99
caliche cemented sand hard		
white	8	107
caliche tan silty hard	9	116
Sand brown cemented	6	122
Sand loose	3	125
stato hard drilled slowly	10	135
caliche - whitish hard	9	144

LOG OF WELL
(FIELD COPIES OF DRILLERS LOGS)


STATE _____ COUNTY _____ NUMBER _____

LOCATION $\frac{1}{4}$ $\frac{1}{4}$ S. 10. T. R.

DRILLER _____ ADDRESS _____

SOURCE OF DATA
(APPROX. CASING RECORD AND ADDITIONAL DATA ON NOTE SHEET)

DRILLER'S DESCRIPTION	THICKNESS DEPTH	844
Sand cemented fine, dilute	Medium	18 162
Sand fine to coarse	Medium	
Cemented bit sandy		11 173
same as above only loose		14 187
White white sandy	Med fine	2 189
Sand fine to coarse gravel		4 193
White sandy clay atks		5 198
Yellow clay sandy silty		9 207
Shale brownish black		13 220+



check log
Kc
from here down had small
pebbles of reworked (Niagara?) (Lawrence?)
white chalk