

DRILLERS TEST LOG

CUSTOMERS NAME Circle A Farms **DATE** 9-29-81
STREET ADDRESS % Royce Williams **TEST #** 1 **E. LOG** yes
CITY & STATE Lakin, Ks. 67860 **DRILLER** Mai
COUNTY Kearny **QUARTER** SW **SECTION** 33 **TOWNSHIP** 22 **RANGE** 37

LOCATION HOUSE WELL

%	FOOTAGE		DESCRIPTION OF STRATA	Static Water Level	
	From	Pay To		Proposed	Well Depth
	0	2	Top Soil		225'
	2	12	Brown clay & caliche		
	12	23	Sand, fine to med. coarse, small to large gravel		
	23	39	Brown sandy clay		
	39	72	Sand, fine to med. coarse, cemented in places, clay stks.		
	72	88	Brown & White clay		
	88	116	Sand, fine to med. & sandy clay & limerock		
	116	128	Brown & Yellow clay, few limerock ledges & sand stks.		
	128	140	Sand, fine to med. Few clay stks.		
	140	175	Sand, fine to med. coarse, small gravel, few brown		
	175	177	Yellow & white soapstone		
60	177	8 185	Sand, fine to med. coarse, small gravel (brown) white rock		
30	185	8 193	Sand, fine to med. & sandy clay		
55	193	5 198	Sand, fine to med. coarse, med. small gravel, few small, few white rock.		
	198	209	Brown & Brown Sandy Clay		
65	209	14 223	Sand, fine to med. coarse, small & few Med. gravel. Gravel with med. white rock.		
	223	225	Soapstone		
	225	230	Shale		
			Total Depth 225'		
			5" Plastic		
			Perf.	Plain	
			225 - 210'	15'	
			210 - 200'		10'
			200 - 185'	15'	
			185 - 0'		185'
				30'	195'
			90 lbs. Revert		
			1/2 gal. chlorine		
			1/3 box Borax		

CROWN CITY, KS
Phone 378-3278

MINKLE DRILLING & SUPPLY CO., INC.
IRRIGATION HEADQUARTERS

SUSLETTE, KS
Phone 675-4311