

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 047 KEARNY NW 1/4 NW 1/4 NW 1/4 26 T 22 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 12 MILES NORTH AND 2 MILES WEST OF LAKIN

2 WATER WELL OWNER: CIRCLE A FARMS
 RR#, St. Address, Box #: RFD Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LAKIN, KS 67860- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 145 ft. below land surface measured on mo/day/yr 12/20/94
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 10 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9.875 in. to 165 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 145 ft. to 165 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 165 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	8	03 SILTY CLAY			
8	18	07 FINE SAND 08 MEDIUM SAND			
18	40	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
40	67	LARGE GRAVEL 09 COARSE SAND 13 FINE GRAVEL			
67	80	01 CLAY 31 CALICHE 04 SANDY CLAY			
80	102	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
102	107	01 CLAY 05 SAND			
107	112	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
112	125	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/20/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/03/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
| COUNTY: 047 KEARNY | NW 1/4 NW 1/4 NW 1/4 | 26 | T 22 S | R 37 W

2 WATER WELL OWNER: | CIRCLE A FARMS | Board of Agriculture, Division of Water Resources
| RR#, St. Address, Box # : RFD | Application Number:
| City, State, ZIP code : LAKIN, KS 67860-

FROM	TO	LITHOLOGIC LOG
125	150	01 CLAY 04 SANDY CLAY
150	154	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
154	162	01 CLAY 04 SANDY CLAY
162	167	01 CLAY
167	180	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/20/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/03/95 under the business name of HENKLE DRILLING & SUPPLY by (signature) Bruce J. Reichmuth