


USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Kerny	Township name	Fraction S15E4	Section number 25	Town number 22	Range number 38
Distance and direction from nearest town or city: 10 mi west-11 mi. north of Lakin, Ks. Street address of well location if in city:				3 Owner of well: High Plains Drilling & Supply, Inc. Address: 402 N 3rd Garden City, Ks. 67846		
Locate with "X" in section below: N  W E S 250' south of center pivot 1 Mile				Sketch map:		
2 Type and color of material				From	To	
				Clay	1	20
				Sandy clay	20	40
				Sand	40	60
				Sand, clay	60	80
				Clay, some sand	80	100
				Clay, some sand	100	120
				Clay, sand	120	140
				Sand fine, med., coarse	140	160
Sand coarse, gravel, loose	160	180				
Sand med., coarse, clay balls	180	200				
Sand coarse	200	220				
Gravel, rock, shale	220	240				
Clay	240	260				
Shale	260	300				
Ordered- set some time last of April (use a second sheet if needed)						
16 Remarks: elevation				4 Well depth: 235 ft. Date of completion 3-17-75 Well diameter 26" in.		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland Level <input type="checkbox"/> Valley				5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
				6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well		
				7 Casing: Material steel Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. _____ Weight 1.79 lbs./ft. 16 in. to 235 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No _____ in. to _____ ft. depth		
				8 Screen: Manufacturer Mill slot Type 6% Dia. 16" Slot/gauze 1/8 Length 2" Set between 175 ft. and 235 ft. Fittings: _____ Gravel pack <input type="checkbox"/> Yes <input type="checkbox"/> No Size range of material _____		
				9 Static water level: 178 ft. below land surface Date 3-17-75		
				10 Pumping level below land surfaces: 188 ft. after 10 hrs. pumping 200 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 455 g.p.m.		
				11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____		
				12 Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade		
				13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From _____ ft. to _____ ft.		
				14 Nearest source of possible contamination: NA ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
				15 Pump: <input type="checkbox"/> Not installed Manufacturer's name Worthington Model number 12L54 HP _____ Volts _____ Length of drop pipe 230 ft. capacity 400 g.m.p. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
16 Remarks: elevation				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. High Plains Drilling & Supply, Inc. Business name _____ License No. 136 Address 402 N 3rd Garden City Ks. Signed Wade E. Burkness Date 4-11-75 Authorized representative		