

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: Kearney Fraction NW 1/4 SW 1/4 SW 1/4 Section Number 20 Township Number T 22 S Range Number R 38 W

Distance and direction from nearest town or city street address of well if located within city?  
PROM KENDALL, KS - 10 MILES NORTH & 1 1/2 MILES EAST

2 WATER WELL OWNER: BURNETT AND HUSER FARMS Martin, Ethel  
 RR#, St. Address, Box #: P.O. BOX 308 Box 669 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: SYRACUSE, KS 67878- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	W	NW	NE
M			
i			
l			
e			
		SW	SE

4 DEPTH OF COMPLETED WELL 280 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 215 ft. below land surface measured on no/day/yr 10/11/94  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 280 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 280 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 235 ft. to 275 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 24 ft. to 280 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 4 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: ABANDONED WELL  
 Direction from well? NORTHEAST How many feet? 30

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	TOPSOIL FINE SAND			
10	24	CALACHIE CLAY			
24	80	FINE - MED SAND GRAVEL			
80	100	YELLOW CLAY			
100	104	FINE SAND			
104	116	YELLOW CLAY			
116	200	FINE - MED SAND			
200	212	YELLOW CLAY			
212	224	MEDIUM SAND CLAY			
224	275	FINE - MED SAND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 10/11/94 and this record is true to the best of my knowledge and belief, Kansas  
 Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 11/02/94  
 under the business name of JOE'S WELL SERVICE, INC. by (signature) Joseph Crick

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: Kearney Fraction NW 1/4 SW 1/4 SW 1/4 Section Number 20 Township Number T 22 S Range Number R 38 W

2 WATER WELL OWNER: BURNETT AND HUSER FARMS  
 RR#, St. Address, Box #: P.O. BOX 308 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: SYRACUSE, KS 67878- Application Number:

FROM	TO	LITHOLOGIC LOG
275	280	YELLOW CLAY
280	300	BLUE SHALE