

WATER WELL RECORD Form WNC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: ; Fraction ; Section Number ; Township Number ; Range Number
 COUNTY: HAMILTON ; SW 1/4 SW 1/4 SE 1/4 ; 14 ; T 22 S ; R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SYRACUSE - ON RD 27 N TO RD 10 - 7 1/2 ON RD 10

2 WATER WELL OWNER: CHEATUM, RICHARD & PATTY
 RR#, St. Address, Box #: BOX 97 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SYRACUSE, KS 67878- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 680 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 262 ft. below land surface measured on mo/day/yr 08/13/10
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 680 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 680 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 580 ft. to 680 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 680 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 10 FINE-MEDSAND			
20	40	10 FINE-MEDSAND 35 CALACHIE 24 THINROCLAYER			
40	100	24 THINROCLAYER 36 BLUE CLAY 16 GRAY CLAY			
100	550	07 BLUE SHALE			
550	560	27 ROCK			
560	680	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/14/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/20/10 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Crick*