

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: Reno Fraction NW 1/4 SE 1/4 NE 1/4 Section Number 25 Township Number T 22 S Range Number R 5 EW

Distance and direction from nearest town or city street address of well if located within city? 1 1/2 South, 2 1/2 West of Buhler Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: Longitude: Elevation: Datum: Data Collection Method:

2 WATER WELL OWNER: Cefiw Oil Co. / Jim & Mary Floyd RR#, St. Address, Box #: P.O. Box 756 / 6710 E. 43rd Ave City, State, ZIP Code: Hartington, NE / Hutchinson, Ks 67502

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N W E S 4 DEPTH OF COMPLETED WELL 102 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... 15..... ft. below land surface measured on mo/day/yr.... 10-10-06 Pump test data: Well water was..... ft. after..... hours pumping..... gpm Est. Yield... N/A gpm: Well water was..... ft. after..... hours pumping..... gpm

5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 5 Wrought Iron 8 Concrete tile CASING JOINTS: Glued.. X.... Clamped..... 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded..... Threaded.....

Blank casing diameter 5..... in. to 42..... ft., Diameter..... in. to ft., Diameter..... in. to ft. Casing height above land surface..... 36..... in., Weight... SDR-26..... lbs./ft. Wall thickness or gauge No.

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass 7 PVC 9 ABS 11 Other (Specify) 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Guazed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw Cut 10 Other (specify)

SCREEN-PERFORATED INTERVALS: From..... 102..... ft. to 42..... ft., From..... ft. to ft. From..... ft. to ft. From..... ft. to ft.

GRAVEL PACK INTERVALS: From..... 102..... ft. to 20..... ft., From..... ft. to ft. From..... ft. to ft. From..... ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other hole plug Grout Intervals: From ft. to ft., From ft. to ft., From 20..... ft. to 0..... ft.

What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage 16 Other (specify below) 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer Storage 15 Oil well/gas well Tank battery

Direction from well? East..... How many feet? ... 200.....

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows include: 0-19 Fine sand, 19-20 Clay, 20-46 Streaky fine sand with clay mixed, 46-51 Clay, 51-63 Fine sand & clay mixed, 63-82 Clay, 82-102 Fine sand mixed with clay.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-10-06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134..... This Water Well Record was completed on (mo/day/year) 10-17-06..... under the business name of Rosencrantz- Bemis by (signature) Gore Alapa

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well. Visit us at http://www.kdhe.state.ks.us/geo/waterwells.