


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Stafford	Fraction 1/4 SE 1/4 NE 1/4	Section number 25	Township number T 23 S	Range number R 11 E
2. Distance and direction from nearest town or city: 10 1/2 miles Northeast of Stafford, KS Street address of well location if in city:			3. Owner of well: Ed Keiter R.R. or street: (?) City, state, zip code: Belpre, KS 67519		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 		
5. Type and color of material			From	To	6. Bore hole dia. 9 in. Completion date 8-3-78 Well depth 60 ft. Pump Set 8-22-78
Top soil			0	3	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
Brown clay			3	30	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Sand & gravel			30	60	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 in. to 50 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. .200
					10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" Slot gauge 1/8" Length 10' Set between 50 ft. and 60 ft. ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200
					11. Static water level: ☐ mo./day/yr. 28'6" below land surface Date 8-3-78
					12. Pumping level below land surface Not checked ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
					13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No ☐ Date ☐
					14. Well head completion: ☐ Pitless adapter 12 inches above grade
					15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: ☐ Not installed Manufacturer's name Berkeley Pump Co. Model number 4BL-15 HP 1 Volts 230 Length of drop pipe 42 ft. capacity 15 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Great Bend, KS 67530 License No. Address 8-23-78 Signed [Signature] Date 8-23-78 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5