

1 LOCATION OF WATER WELL: County: <u>Stafford</u> Fraction <u>1/4 SE 1/4 NW 1/4 SE 1/4</u> Section Number <u>33</u> Township No. <u>T 23 S</u> Range Number <u>R 13</u> ☐ E ☒ W																																								
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ <u>Approximately 1/4 mile east of intersection of N Prairie St. and E 5th Ave. in St. John.</u>																																								
2 WATER WELL OWNER: <u>City of St. John</u> RR#, Street Address, Box #: <u>P.O. Box 367</u> City, State, ZIP Code : <u>St. John, KS 67576</u>																																								
Global Positioning System (GPS) information: Latitude: <u>38.004535</u> (in decimal degrees) Longitude: <u>-98.751978</u> (in decimal degrees) Elevation: <u>unknown</u> Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: <u>WAAS</u>) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																								
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W E --NW-- --NE-- --SW-- --SE-- S -----1 mile-----	4 DEPTH OF COMPLETED WELL <u>113</u> ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL <u>18.5</u> ft. below land surface measured on mo/day/yr <u>7/27/11</u> Pump test data: Well water was <u>not checked</u> ft. after _____ hours pumping _____ gpm EST. YIELD _____ gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter <u>5</u> in. to <u>116</u> ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Observation Well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☐ Yes ☒ No																																							
	5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter <u>2</u> in. to <u>101</u> ft., Diameter _____ in. to _____ ft., Diameter _____ in. to _____ ft. Casing height above land surface <u>24</u> in., Weight <u>.70</u> lbs./ft., Wall thickness or gauge No. <u>.154</u> TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From <u>101</u> ft. to <u>111</u> ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From <u>97</u> ft. to <u>111</u> ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From _____ ft. to _____ ft., From <u>0</u> ft. to <u>97</u> ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None Known Direction from well _____ Distance from well _____																																								
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th></tr></thead><tbody><tr><td>0</td><td>2</td><td>Topsoil</td></tr><tr><td>2</td><td>10</td><td>Clay, brown</td></tr><tr><td>10</td><td>30</td><td>Sand, gravel, fine to coarse</td></tr><tr><td>30</td><td>50</td><td>Sand, gravel, fine to coarse, thin yellow clay streaks</td></tr><tr><td>50</td><td>70</td><td>Sand, fine to coarse, some clay pieces</td></tr><tr><td>70</td><td>80</td><td>Sand, gravel, fine to coarse, caliche</td></tr><tr><td>80</td><td>95</td><td>Sand, fine to coarse, fine to medium gravel</td></tr><tr><td>95</td><td>96</td><td>Clay, gray</td></tr></tbody></table>	FROM	TO	LITHOLOGIC LOG	0	2	Topsoil	2	10	Clay, brown	10	30	Sand, gravel, fine to coarse	30	50	Sand, gravel, fine to coarse, thin yellow clay streaks	50	70	Sand, fine to coarse, some clay pieces	70	80	Sand, gravel, fine to coarse, caliche	80	95	Sand, fine to coarse, fine to medium gravel	95	96	Clay, gray	<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>96</td><td>112</td><td>Sand, gravel, fine to coarse, dakota drift</td></tr><tr><td>112</td><td>115</td><td>Weathered shale, clay, gray</td></tr><tr><td>115</td><td>116</td><td>Clay, gray</td></tr></tbody></table>	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	96	112	Sand, gravel, fine to coarse, dakota drift	112	115	Weathered shale, clay, gray	115	116	Clay, gray
FROM	TO	LITHOLOGIC LOG																																						
0	2	Topsoil																																						
2	10	Clay, brown																																						
10	30	Sand, gravel, fine to coarse																																						
30	50	Sand, gravel, fine to coarse, thin yellow clay streaks																																						
50	70	Sand, fine to coarse, some clay pieces																																						
70	80	Sand, gravel, fine to coarse, caliche																																						
80	95	Sand, fine to coarse, fine to medium gravel																																						
95	96	Clay, gray																																						
FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																						
96	112	Sand, gravel, fine to coarse, dakota drift																																						
112	115	Weathered shale, clay, gray																																						
115	116	Clay, gray																																						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>7/27/11</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>185</u> This Water Well Record was completed on (mo/day/year) <u>8/5/11</u> under the business name of <u>Clarke Well & Equipment, Inc.</u> by (signature) <u>[Signature]</u>																																								

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.