

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Stafford		Fraction: 1/4 SW 1/4 NE 1/4 SE 1/4	Section Number: 33	Township No.: T 23 S	Range Number: R 13 E W																																													
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection; If at owner's address, check here ☐ Approximately 0.25 miles west of intersection Hwy 281 & 5th Ave. in St. John.			Global Positioning System (GPS) information: Latitude: 38.004147 (in decimal degrees) Longitude: -98.75149 (in decimal degrees) Elevation: Unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																															
2 WATER WELL OWNER: City of St. John RR#, Street Address, Box #: P.O. Box 367 City, State, ZIP Code: St. John, KS 67576																																																		
3 LOCATE WELL WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 117 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 26 ft. below land surface measured on mo/day/yr 08/21/13 Pump test data: Well water was <u>not checked</u> ft. after _____ hours pumping _____ gpm EST. YIELD _____ gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 24 in. to 117 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☒ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																
5 TYPE OF CASING USED: ☒ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☒ Welded ☐ Threaded Casing diameter 10 in. to 27.50 ft., Diameter 10 in. to 107.50 ft., Diameter _____ in. to _____ ft. Casing height above land surface 18 in., Weight 12.23 lbs./ft., Wall thickness or gauge No. .593 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☒ Stainless Steel ☐ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☒ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 107.50 ft. to 115.50 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 99 ft. to 117 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																		
6 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From 6 ft. to 28 ft., From 28 ft. to 99 ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well _____ <table border="1" style="width:48%;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr><td>0</td><td>3</td><td>Topsoil</td></tr> <tr><td>3</td><td>10</td><td>Clay, brown</td></tr> <tr><td>10</td><td>62</td><td>Sand & gravel, fine to medium</td></tr> <tr><td>62</td><td>65</td><td>Clay, brown</td></tr> <tr><td>65</td><td>96</td><td>Sand & gravel, fine to medium</td></tr> <tr><td>96</td><td>115.5</td><td>Sand & gravel, fine to medium to coarse</td></tr> <tr><td>115.5</td><td>117</td><td>Clay, brown</td></tr> </tbody> </table> <table border="1" style="width:48%;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	0	3	Topsoil	3	10	Clay, brown	10	62	Sand & gravel, fine to medium	62	65	Clay, brown	65	96	Sand & gravel, fine to medium	96	115.5	Sand & gravel, fine to medium to coarse	115.5	117	Clay, brown	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																		
FROM	TO	LITHOLOGIC LOG																																																
0	3	Topsoil																																																
3	10	Clay, brown																																																
10	62	Sand & gravel, fine to medium																																																
62	65	Clay, brown																																																
65	96	Sand & gravel, fine to medium																																																
96	115.5	Sand & gravel, fine to medium to coarse																																																
115.5	117	Clay, brown																																																
FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 08/21/13 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 09/05/13 under the business name of Clarke Well & Equipment, Inc. by (signature)																																																		
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html																																																		