


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 1/4 CSW 1/4	Section number 5	Township number T 23 S	Range number R 13 E
2. Distance and direction from nearest town or city: 5 mi. North of St. John, KS Street address of well location if in city:				3. Owner of well: Kurt Rugan R.R. or street: Route 2 City, state, zip code: Ellinwood, KS 67526		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 24 in. Completion date 3-10-76 Well depth 100 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material				From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Top soil				0	3	9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia 16 in. to 60 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.
Sandy clay				3	8	10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot gauge 1/8 Length 40' Set between 60 ft. and 100 ft. ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200
Brown & gray clay & limestone				8	34	11. Static water level: ☐ mo./day/yr. 22 1/2 ft. below land surface Date 1-26-76
Sand & clay streaks				34	41	12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
Sand & gravel				41	54	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐
Yellow clay				54	55	14. Well head completion: ☐ Pitless adapter 12 Inches above grade
Sand & gravel				55	77	15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
Gray clay & gravel streaks				77	80	16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No
Sand & gravel				80	100	17. Pump: ☐ Not installed Manufacturer's name FMC Corp./Peerless Model number 12LB-3 HP 80 Volts ☐ Length of drop pipe 70 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed [Signature] Date 4-14-76 Authorized representative
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5