


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County Stafford		Fraction SW 1/4 SW 1/4 NE 1/4	Section number 20	Township number T 23 S	Range number R 13 E																																	
1. Location of well: Approx. 1 1/2 mile North of St. John, KS Street address of well location if in city:			3. Owner of well: Ben Schulz R.R. or street: Route 3 City, state, zip code: St. John, KS 67576																																			
4. Locate with "X" in section below: 			Sketch map:																																			
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th style="width:55%;">5. Type and color of material</th><th style="width:10%;">From</th><th style="width:10%;">To</th></tr></thead><tbody><tr><td>Sandy top soil</td><td>0</td><td>3</td></tr><tr><td>Sand & gravel</td><td>3</td><td>19</td></tr><tr><td>Yellow clay</td><td>19</td><td>20</td></tr><tr><td>Sand & gravel</td><td>20</td><td>39</td></tr><tr><td>Brown & white hard clay</td><td>39</td><td>47</td></tr><tr><td>Sand</td><td>47</td><td>50</td></tr><tr><td>White clay - Hard</td><td>50</td><td>55</td></tr><tr><td>Sand & gravel</td><td>55</td><td>62</td></tr><tr><td>White clay</td><td>62</td><td>64</td></tr><tr><td>Sand & gravel</td><td>64</td><td>72</td></tr></tbody></table>			5. Type and color of material	From	To	Sandy top soil	0	3	Sand & gravel	3	19	Yellow clay	19	20	Sand & gravel	20	39	Brown & white hard clay	39	47	Sand	47	50	White clay - Hard	50	55	Sand & gravel	55	62	White clay	62	64	Sand & gravel	64	72	6. Bore hole dia. <u>24</u> in. Completion date <u>7-6-79</u> Well depth <u>73</u> ft. Pump Set <u>7-17-79</u>		
			5. Type and color of material	From	To																																	
			Sandy top soil	0	3																																	
			Sand & gravel	3	19																																	
			Yellow clay	19	20																																	
			Sand & gravel	20	39																																	
			Brown & white hard clay	39	47																																	
			Sand	47	50																																	
			White clay - Hard	50	55																																	
			Sand & gravel	55	62																																	
White clay	62	64																																				
Sand & gravel	64	72																																				
7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary																																						
8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																						
9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>23</u> ft. depth Wall Thickness: <u>inches</u> or Dia. <u>in.</u> to <u>ft.</u> depth Gage No. <u>7 ga.</u>																																						
10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Double-slot</u> Dia. <u>16"</u> <u>Slot</u> gauze <u>1/8"</u> Length <u>50'</u> Set between <u>23</u> ft. and <u>73</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8-200</u>																																						
11. Static water level: <u>11' 9"</u> ft. below land surface Date <u>5-23-79</u> 12. Pumping level below land surfaces: <u>N/C</u> <u>ft.</u> after <u>hrs.</u> pumping <u>g.p.m.</u> <u>ft.</u> after <u>hrs.</u> pumping <u>g.p.m.</u> Estimated maximum yield <u>g.p.m.</u>																																						
13. Water sample submitted: <u>mo./day/yr.</u> <u>Yes</u> ☒ <u>No</u> Date <u>5-23-79</u>																																						
14. Well head completion: <u>12</u> inches above grade ☐ Pitless adapter																																						
15. Well grouted? <u>Yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.																																						
16. Nearest source of possible contamination: <u>FIELD</u> ft. <u>Direction</u> <u>Type</u> Well disinfected upon completion? <u>Yes</u> ☒ <u>No</u>																																						
17. Pump: <u>Not installed</u> Manufacturer's name <u>Peerless Pump Co.</u> Model number <u>12MB-4</u> HP <u>50</u> Volts <u>460</u> Length of drop pipe <u>60</u> ft. capacity <u>1000</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																						
18. Elevation:																																						
19. Remarks:																																						
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u>7-27-79</u> Address <u>7-27-79</u> Signed <u>[Signature]</u> Date <u>7-27-79</u> Authorized representative																																						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5