


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction SW 1/4 SW 1/4 SW 1/4	Section number 26	Township number T 23 S	Range number R 13 E
2. Distance and direction from nearest town or city: 1 1/2 mi. East of St. John, KS Street address of well location if in city:				3. Owner of well: Kansas State University R.R. or street: AG-Engineering Dept. City, state, zip code: Manhattan, KS 66502		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 9 in. Completion date 6-1-76 Well depth 50 ft.		
		7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
		9. Casing: Material Styrene Weight: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 in. to 40 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gauge No. 200#				
5. Type and color of material				From	To	10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" ☒ Slot gauge 1/8 Length 10' Set between 40 ft. and 50 ft. ft. and ft. Gravel pack? Yes Size range of material 3/8-200
Top soil				0	3	11. Static water level: _____ mo./day/yr. 11 1/2 ft. below land surface Date 5-11-76
Sandy clay				3	16	12. Pumping level below land surfaces: N/C _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
Sand & gravel				16	35	13. Water sample submitted: _____ mo./day/yr. Yes ☐ No ☒ Date _____
Yellow clay				35	38	14. Well head completion: _____ Pitless adapter 12 Inches above grade
Sand & gravel				38	50	15. Well grouted? Yes With: ☒ Neat cement _____ Bentonite _____ Concrete _____ Depth: From 0 ft. to 10 ft.
						NONE KNOWN 16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? ☒ Yes ☒ No
						17. Pump: _____ Not installed Manufacturer's name Berkeley Pump Co. Model number 4AM-11 HP 1/2 Volts 230 Length of drop pipe 60 ft. capacity 12 g.p.m. Type: ☒ Submersible _____ Turbine _____ Jet _____ Reciprocating _____ Centrifugal _____ Other
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: This is one of two wells drilled in almost the exact location.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed D.W. Clarke Date 6-1-76 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5