

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Stafford	Fraction XX XX NE 1/4	Section number 27	Township number T 23 S	Range number R 13 E
2. Distance and direction from nearest town or city: 2 1/2 miles Northeast of St. John, KS Street address of well location if in city:			3. Owner of well: X Gilbert Sayler R.R. or street: 534 West 4th City, state, zip code: St. John, KS 67576		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: NW NE SW SE X		
5. Type and color of material			6. Bore hole dia. 24 in. Completion date 8-23-77 Well depth 90 ft.		
Top soil & brown sandy clay			7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Sand & gravel			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Brown clay			9. Casing: Material steel Height Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 50 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.		
Sand & gravel & thin clay streaks at 60'-63'-73'			10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot/gauze 1/8 Length 40' Set between ☐ ft. and ☐ ft. ☐ ft. and ☐ ft. Gravel pack? yes Size range of material 3/8-200		
			11. Static water level: ☐ ma./day/yr. 15'5" ft. below land surface Date 8-16-77		
			12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
			13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date		
			14. Well head completion: ☐ Pitless adapter 12 inches above grade		
			15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
			16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
			17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Model number 12LB-3 HP 80 Volts --- Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 8-24-77 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5