

OFFICE USE ONLY

T

R

E/W

SEC.

1/4

1/4

1/4

1/4

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: STAFFORD		SW 1/4 SW 1/4 SW 1/4	33	T 23 S	R 13 E/W
Distance and direction from nearest town or city street address of well if located within city? 1111111111 512 N. BROADWAY					
2 WATER WELL OWNER: JIM KIRKHAM					
RR#, St. Address, Box # : 512 N. BROADWAY			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : ST. JOHN, KS 67576			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 60 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 22' 6" ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 9 in. to ft. and in. to ft.			
WELL WATER TO BE USED AS:		5 Public water supply 8 Air conditioning 11 Injection well ☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted		Water Well Disinfected? Yes ☒ No			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)		5 Wrought iron	
☒ PVC		4 ABS		6 Asbestos-Cement	
				7 Fiberglass	
Blank casing diameter 5 in. to 50 ft. Dia		in. to ft. Dia		CASING JOINTS: Glued ☒ Clamped	
Casing height above land surface 24 in. weight		lbs./ft. Wall thickness or gauge No.		Welded	
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC		10 Asbestos-cement	
1 Steel		3 Stainless steel		5 Fiberglass	
2 Brass		4 Galvanized steel		6 Concrete tile	
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped		8 Saw cut	
1 Continuous slot		☒ Mill slot		9 Drilled holes	
2 Louvered shutter		4 Key punched		10 Other (specify)	
SCREEN-PERFORATED INTERVALS:		From 50 ft. to 60 ft.		From ft. to ft.	
		From ft. to ft.		From ft. to ft.	
GRAVEL PACK INTERVALS:		From 23 ft. to 60 ft.		From ft. to ft.	
		From ft. to ft.		From ft. to ft.	
6 GROUT MATERIAL:					
1 Neat cement		2 Cement grout		☒ Bentonite	
4 Other					
Grout Intervals: From 3 ft. to 23 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines		7 Pit privy	
2 Sewer lines		5 Cess pool		8 Sewage lagoon	
3 Watertight sewer lines		6 Seepage pit		9 Feedyard	
				10 Livestock pens	
				11 Fuel storage	
				12 Fertilizer storage	
				13 Insecticide storage	
				14 Abandoned water well	
				15 Oil well/Gas well	
				16 Other (specify below)	
				NONE	
Direction from well? How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	TOP SOIL			
3	17	CLAY			
17	38	SAND & GRAVEL			
38	42	CLAY			
42	60	GRAVEL			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-29-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 462 This Water Well Record was completed on (mo/day/yr) 8-13-94 under the business name of SAM'S WATER WELL SERVICE by (signature) <i>Lara Ray Kern</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					