


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction NE 1/4 SW 1/4 SE 1/4	Section number 21	Township number T 23 S R 14	Range number 14
2. Distance and direction from nearest town or city: 6 1/2 miles Northwest of St. John, KS Street address of well location if in city:				3. Owner of well: Ward Beaver R.R. or street: Route 3 City, state, zip code: St. John, KS 67576		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 17 in. Completion date 4-14-78 Well depth 52 ft. (Well Drilled)		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil		0	2	9. Casing: Material Plastic Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 3.14 lbs./ft. Dia. 8 in. to 30 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 199		
Sandy clay		2	9	10. Screen: Manufacturer's name Johns-Manville Type Slotted Dia. 8" Slot gauge 1/8" Length 22' Set between 30 ft. and 52 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 3/8-200		
Sand		9	16	11. Static water level: ☐ mo./day/yr. 9 ft. below land surface Date 4-14-78		
Sandy clay		16	19	12. Pumping level below land surfaces: None N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
Sand & gravel		19	51	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
Brown clay		51	52	14. Well head completion: ☐ Pitless adapter 12 Inches above grade		
				15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name Berkeley Pump Co. Model number GS2AM-1 HP 3 Volts 460 Length of drop pipe 42 ft. capacity 200 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Great Bend, KS 67530 License No. Address 4-26-78 Signed [Signature] Date 4-26-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5