


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Pawnee</b>	Fraction <b>N<math>\frac{1}{2}</math></b> <b>1/4 1/4 SE 1/4</b>	Section number <b>26</b>	Township number <b>T 23</b>	Range number <b>S R 15 EW</b>
2. Distance and direction from nearest town or city: <del>18 1/2 miles Southeast of Larned, KS</del> Street address of well location if in city: <b>Approx 11 mi So + 8 1/2 East of Larned</b>			3. Owner of well: <b>Russell Walker</b> R.R. or street: <b>Rural Route</b> City, state, zip code: <b>Macksville, KS 67557</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>24</b> in. Completion date <b>10-13-78</b> Well depth <b>64</b> ft.		
				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Top soil		0	3	9. Casing: Material <b>steel</b> Height <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>30.3</b> lbs./ft. Dia. <b>16</b> in. to <b>40</b> ft. depth Wall Thickness: inches or Dia. <b>16</b> in. to <b>64</b> ft. depth gage No. <b>7 ga.</b>		
Brown clay		3	8	10. Screen: Manufacturer's name <b>Cook</b> Type <b>Cook "V" wire</b> Dia. <b>16"</b> Slot/gauze <b>1/8"</b> Length <b>20'</b> Set between <b>40</b> ft. and <b>60</b> ft. Gravel pack? <b>Yes</b> Size range of material <b>3/8-200</b>		
Sandy clay & sand stone & sand streaks		8	40	11. Static water level: <b>18'6"</b> ft. below land surface Date <b>10-13-78</b> mo./day/yr.		
Sand & gravel		40	59	12. Pumping level below land surfaces: <b>N/C</b> ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.		
Brown clay		59	64	13. Water sample submitted: ____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ____		
				14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> inches above grade		
				15. Well grouted? <b>Yes</b> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.		
				16. Nearest source of possible contamination: <b>FIELD</b> ft. ____ Direction ____ Type ____ Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
				17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name ____ Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Clarke Well &amp; Eq., Inc. 185</b> Business name <b>Great Bend, KS 67530</b> License No. <b>3-15-79</b> Address <b>Great Bend, KS 67530</b> Signed <b>[Signature]</b> Date <b>10-13-78</b> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		Holding for pump installation - No Pump installed as of this date.				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5