


1 LOCATION OF WATER WELL: County: Pawnee <u>073</u> Distance and direction from nearest town or city street address of well if located within city? Approx. 4 miles North of Macksville, KS		Fraction <u>Near Center of W₁</u> of <u>1/4</u> <u>NE</u> <u>XX</u> <u>NE</u> <u>1/4</u> Section Number <u>28</u>		Township Number T <u>23</u> S		Range Number R <u>15</u> <u>EW</u>	
2 WATER WELL OWNER: Terry Sallee RR#, St. Address, Box # : Route 1 City, State, ZIP Code : Macksville, KS 67557				Board of Agriculture, Division of Water Resources Application Number: 36,970			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 61 ft. ELEVATION: unknown Depth(s) Groundwater Encountered 1. 21 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 21 ft. below land surface measured on mo/day/yr 3/23/88 Pump test data: Well water was not ck'd ft. after hours pumping gpm Est. Yield 500 gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 24 in. to 61 ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X					
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 2 PVC 4 ABS Blank casing diameter 16 in. to 40 ft., Dia Casing height above land surface 24 in., weight 36.87 lbs./ft. Wall thickness or gauge No. 219 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 23 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes SCREEN-PERFORATED INTERVALS: From 41 ft. to 60 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 60 ft., From ft. to ft. From ft. to ft., From ft. to ft.				CASING JOINTS: Glued Clamped Welded X Threaded			
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) Direction from well? all How many feet? field				13 Insecticide storage			
FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG					
0	26 07	Fine sand & topsoil & sandy clay					
26	36 01	Clay, brown, very soft, sandy					
36	55	Sand & gravel, med. to fine, clean (more fine) w/a lot of thin clay streaks					
55	60 17	Sand & gravel, med. to coarse, clean with thin clay streaks					
60	61 01	White & brown clay					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3/23/88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 4/19/88 under the business name of Clarke Well & Equipment, Inc. by (signature)							
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.							

OFFICE USE ONLY

T

R

EOD

SEC.

28

11

14

15

16

17