

County	Harvey	Fraction	NW ¹ / ₄ NW ¹ / ₄ NE ¹ / ₄	Section number	17	Township number	T 23 S R 2	Range number	2	
2. Distance and direction from nearest town or city:		3 mi N 2½ W		3. Owner of well:		Randy Chapel				
Street address of well location if in city:		of Halstead, Ks.		R.R. or street:		Box 94B RR2				
				City, state, zip code:		Burton, Ks. 67020				
4. Locate with "X" in section below:			Sketch map:			6. Bore hole dia. 16 in. Completion date				
						Well depth 6-15-76				
5. Type and color of material			From			To			7. Cable tool Rotary Driven Dug Hollow rod Jetted Bored Reverse rotary	
Topsoil - black			0			3			8. Use: Domestic Public supply Industry Irrigation Air conditioning Stock Lawn Oil field water Other	
Clay - dk gray			3			8			9. Casing: Material PLS Height: Above or below Threaded Welded Surface 16 in. RMP PVC Weight 195 lbs./ft. Dia. 6 in. to 42 ft. depth Wall Thickness: inches or Dia. in. to ft. depth gage No. 200	
Sand - yellow - Fine			8			31			10. Screen: Manufacturer's name J & L Type RMP Dia. 6" Slot/gauze 3/32" Length 10' Set between 32 ft. and 42 ft. Gravel pack? yes Size range of material F-5"	
Sand Coarse gray			31			42			11. Static water level: mo./day/yr. 14 ft. below land surface Date 6-15-76	
									12. Pumping level below land surfaces: 20.5 ft. after 1 hrs. pumping 23 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 30 g.p.m.	
									13. Water sample submitted: mo./day/yr. Yes X No Date	
									14. Well head completion: Pitless adapter 16 Inches above grade	
									15. Well grouted? yes With: Neat cement Bentonite Concrete Depth: From 3 ft. to 13 ft.	
									16. Nearest source of possible contamination: 75' Direction NE Type septic Well disinfected upon completion? X Yes No	
									17. Pump: Not installed Manufacturer's name Aeromotor Model number DSJ HP 12 Volts 230 Length of drop pipe 35 ft. capacity 10 g.p.m. Type: Submersible Turbine Jet Reciprocating Centrifugal Other	
18. Elevation:			19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Miller Water Well Serv. 137 Business name License No. Address Hutchinson, Ks. Signed Joe Miller Date Authorized representative				