

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Harvey</u>		<u>NE 1/4 NE 1/4 NW 1/4</u>	<u>17</u>	T <u>23</u> S	R <u>2</u> EW <u>1</u>
Distance and direction from nearest town or city street address of well if located within city? <u>6 miles NW of Holstead</u>					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # :		Application Number:			
City, State, ZIP Code :					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>48</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. <u>30</u> ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>22</u> ft. below land surface measured on mo/day/yr <u>9-7-88</u>			
		Pump test data: Well water was <u>48</u> ft. after <u>2</u> hours pumping <u>25</u> gpm			
		Est. Yield <u>20</u> gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>11</u> in. to <u>48</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		<input checked="" type="checkbox"/> Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No <u>X</u>; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes <u>X</u> No			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <u>X</u> Clamped <input checked="" type="checkbox"/> <u>PVC</u> 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded					
Blank casing diameter <u>6</u> in. to <u>38</u> ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface <u>18</u> in., weight <u>3.36</u> lbs./ft. Wall thickness or gauge No. <u>255</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped <u>Shop</u> <input checked="" type="checkbox"/> <u>Saw cut</u> <u>1030</u> 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From <u>38</u> ft. to <u>48</u> ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From <u>20</u> ft. to <u>48</u> ft., From ft. to ft.					
6 GROUT MATERIAL:					
1 Neat cement 2 Cement grout <input checked="" type="checkbox"/> <u>Bentonite</u> 4 Other Grout intervals: From <u>0</u> ft. to <u>20</u> ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well <input checked="" type="checkbox"/> <u>Sewer lines</u> 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage					
Direction from well? <u>North</u> How many feet? <u>150'</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
<u>0</u>	<u>5</u>	<u>loam to dune sand</u>			
<u>5</u>	<u>9</u>	<u>dune sand</u>			
<u>9</u>	<u>15</u>	<u>red brown clay</u>			
<u>15</u>	<u>20</u>	<u>sandy brown clay</u>			
<u>20</u>	<u>26</u>	<u>grey clay</u>			
<u>26</u>	<u>30</u>	<u>sandy grey clay</u>			
<u>30</u>	<u>46</u>	<u>sand med fine to coarse</u>			
<u>46</u>	<u>48</u>	<u>grey clay</u>			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>(1) constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>9-7-88</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>452</u> This Water Well Record was completed on (mo/day/yr) <u>10-3-88</u>					
under the business name of <u>United Water Well Pump</u> by (signature) <u>Raul B...</u>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answer. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4