

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: HARVEY		NE 1/4 NW 1/4 SE 1/4	35	T 23 S	R 2 E
Distance and direction from nearest town or city street address of well if located within city? 100 MAIN, HALSTEAD, KS					
2 WATER WELL OWNER: WILDA MOFFATT					
RR#, St. Address, Box # : 100 MAIN			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : HALSTEAD, KS 67056			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 23.5 ft. ELEVATION: 1390.67			
		Depth(s) Groundwater Encountered 1. 18.0 ft. 2. - ft. 3. - ft.			
		WELL'S STATIC WATER LEVEL 17.30 ft. below land surface measured on mo/day/yr 4-25-93			
		Pump test data: Well water was - ft. after - hours pumping - gpm			
		Est. Yield - gpm: Well water was - ft. after - hours pumping - gpm			
		Bore Hole Diameter 8 in. to 25.5 ft. and - in. to - ft.			
		WELL WATER TO BE USED AS:			
		1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? Yes - No X ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes - No X			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued - Clamped - 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded - 7 Fiberglass Threaded X					
Blank casing diameter 2 in. to 13.5 ft. Dia - in. to - ft. Dia - in. to - ft.					
Casing height above land surface -3.6 in., weight - lbs./ft. Wall thickness or gauge No. 40					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) - 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
7 Torch cut 10 Other (specify) -					
SCREEN-PERFORATED INTERVALS: From 23.5 ft. to 13.5 ft. From - ft. to - ft.					
GRAVEL PACK INTERVALS: From 25.5 ft. to 11.5 ft. From - ft. to - ft.					
6 GROUT MATERIAL: 1 Heat cement 2 Cement grout 3 Bentonite 4 Other -					
Grout Intervals: From 11.5 ft. to 0 ft. From - ft. to - ft. From - ft. to - ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
13 Insecticide storage					
Direction from well? EAST How many feet? 500					
FROM		TO		LITHOLOGIC LOG	
FROM		TO		PLUGGING INTERVALS	
0		1.5		TOPSOIL	
1.5		7.0		DARK BROWN S. 1/4 CLAY	
7.0		16.5		Grey BROWN S. 1/4 CLAY	
16.5		21.0		Grey BROWN Sandy S. 1/4 CLAY	
21.0		23.5		Grey FINE GRAIN SAND w/ some clay	
23.5		25.5		BROWN FINE GRAIN SAND	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4/21/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 4110 This Water Well Record was completed on (mo/day/yr) 7/23/93 under the business name of Terrace Consultants Inc by (signature) Rudolf D. M...					