


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Harvey</u>	<u>NE 1/4 SE 1/4 SE 1/4</u>	<u>34</u>	<u>T 23 S</u>	<u>R 2 EW</u>

Distance and direction from nearest town or city street address of well if located within city?

515 Industrial Rd in Halstead

2 WATER WELL OWNER:	<u>Idaho Timber</u> <u>515 Industrial Rd</u> <u>Halstead, KS 67056</u>	Board of Agriculture, Division of Water Resources Application Number:
---------------------	--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL <u>82</u> ft. ELEVATION:
--	--



Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft.

WELL'S STATIC WATER LEVEL 19 ft. below land surface measured on mo/day/yr 4-15-04

Pump test data: Well water was 23 ft. after 14 hours pumping 3.8 gpm

Est. Yield gpm: Well water was ft. after hours pumping gpm

WELL WATER TO BE USED AS:

5 Public water supply	8 Air conditioning	11 Injection well
1 Domestic	3 Feedlot	6 Oil field water supply
2 Irrigation	4 Industrial	9 Dewatering
	<u>7</u> Domestic (lawn & garden)	10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes No

5 TYPE OF BLANK CASING USED:	5 Wrought iron 6 Asbestos-Cement 7 Fiberglass	8 Concrete tile 9 Other (specify below)
------------------------------	---	--

CASING JOINTS: Glued X Clamped
 Welded
 Threaded

Blank casing diameter 5 in. to 72 ft., Dia in. to ft., Dia in. to ft.

Casing height above land surface 12 in., weight 2.29 lbs./ft. Wall thickness or guage No. 16.0

TYPE OF SCREEN OR PERFORATION MATERIAL:	5 Fiberglass 6 Concrete tile	8 RMP (SR) 9 ABS
---	---------------------------------	---------------------

1 Steel 3 Stainless Steel 10 Asbestos-Cement
 2 Brass 4 Galvanized Steel 11 Other (Specify)
 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot	3 Mill slot	5 Guazed wrapped	<u>8</u> Saw cut	11 None (open hole)
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes	
		7 Torch cut	10 Other (specify)	

SCREEN-PERFORATED INTERVALS: From 72 ft. to 82 ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 22 ft. to 50 ft., From ft. to ft.

From 55 ft. to 85 ft., From ft. to ft.

6 GROUT MATERIAL:	1 Neat cement 2 Cement grout 3 Bentonite	4 Other
-------------------	--	---------------

Grout Intervals: From 2 ft. to 22 ft., From 50 ft. to 55 ft., From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
<u>3</u> Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	

Direction from well? N How many feet? 12

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
<u>0</u>	<u>17</u>	<u>Gr Clay</u>			
<u>17</u>	<u>25</u>	<u>F Sand - Grey</u>			
<u>25</u>	<u>35</u>	<u>F-M Sand - Grey</u>			
<u>35</u>	<u>47</u>	<u>Sand + Sm Gravel</u>			
<u>47</u>	<u>55</u>	<u>Gr Clay</u>			
<u>55</u>	<u>60</u>	<u>Br Clay</u>			
<u>60</u>	<u>70</u>	<u>F-M Sand</u>			
<u>70</u>	<u>83</u>	<u>C Sand</u>			
<u>83</u>	<u>85</u>	<u>Br + Gr Clay</u>			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>(1)</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>4-15-04</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No <u>447</u> This Water Well Record was completed on (mo/day/yr) <u>5-10-04</u> under the business name of <u>Miller Drilling</u> by (signature) <u>[Signature]</u>
--