

WATER WELL RECORD

DRILLERS LOG OF WELL

FROM (FT.)	TO (FT.)	KIND OF MATERIAL, COLOR, ETC. (NOTE WATER ZONES, AMOUNT, QUALITY)
5-12	12	loam to clay
12-16	16	Sandy clay
16-17	17	clay
17-20	20	Sand med coarse
20-21	21	clay
22-23	23	hard white rock
23-25	25	clay
25-27	27	white shale
27-28	28	sand
28-31	31	Shale
31-45	45	clay with shale ledges And some sand interspersed
46-50	50	clay & white shale mixed
50-64	64	compact sand - had to drill it
64-68	68	brownish-white shale
68-70	70	clay &
70-80	80	hard clay

Well Owner Loney Legasick
 Address R.R. #1 Newton
 Drilling Contractor PAUL'S TAIL

Date Drilled 4/26/74
 Method of Drilling Rotary
 (Cable tool, rotary, reverse rotary, etc.)
 Casing Schedule New - 80' - 6"
 (Amount, Size, Setting—New, Used—Steel, Galv.—Gage or Weight)

Screen Data (if any): 20' - 6" 1/16 slot
 (Length, Diameter, Slot Size, Setting)
40' - 60'

Measured depth to water on completed well (Static Level) is
38' ft. below Top of casing
 (Land Surface, Top of Casing, Etc.)

TESTED YIELD: 20 gallons per Min
 (Min., Hour)
 as determined by Test pumping
 (Bailing/Test Pumping, Etc.)


DRAWDOWN: 2' ft. after 1 1/2 hrs.
 pumping at 20 gal. per minute.

REMARKS:

SALT - Chlorides
1455' white clay
harder on intermediate
harder, increasing toward

LOCATION OF WELL Topographic Sheet
 [Show location in Section Plat] Elev.

N
↑



NE x SW x Sec. 1
 T. 23 S., R. 2 EW
 County HARVEY