

WATER WELL RECORD

DRILLERS LOG OF WELL

FROM (FT.)	TO (FT.)	KIND OF MATERIAL, COLOR, ETC. (NOTE WATER ZONES, AMOUNT, QUALITY)
0	15	dune sand to clay
15	20	Sandy clay
20	25	dark clay
25	27	clay w / some fine sand
27	31	Sand w/ clay mix
31	35	clay w/ some sand
35	38	clay
38	41	Sand + thin white shale
41	42	white hard shale
42	46	blue hard clay
46	54	white grey clay
54	56	light white shale
		With thin sand
56	60	grey sandy clay
60	61	white hard shale
61	63	brown shale + sand
		layers
63	85	- compacted grey sand
		drillable
85	88	dark shale

Well Owner HU Co. PARK

Address _____

Drilling Contractor PAUL'S INC

Date Drilled 4/25/74

Method of Drilling Rotary
 (Cable tool, rotary, reverse rotary, etc.)

Casing Schedule New 8"
 (Amount, Size, Setting—New, Used—Steel, Galv.—Gage or Weight)
PVC - plastic #100

Screen Data (if any): 30' - 8" 1/8
 (Length, Diameter, Slot Size, Setting)
Slot - 58 - 88

Measured depth to water on completed well (Static Level) is
14 ft. below Top of casing
 (Land Surface, Top of Casing, Etc.)

TESTED YIELD: 20 gallons per MIN
 (Min., Hour)

as determined by test pumping
 (Bailing, Test Pumping, Etc.)


DRAWDOWN: 4 ft. after 1 1/2 hrs.

pumping at 20 gal. per minute.

REMARKS: 14' 5" log
some water
14' 5" sand

LOCATION OF WELL Topographic Sheet _____

[Show location in Section Plat] Elev. _____



NW & SE & Sec. 6

T. 23 S., R. 2 W

County HARVEY